

BID PROPOSAL
MILL CREEK ROAD MP 1.10 TO MP 3.96
STPR--K364(007) TA-7345, RAP 3616-01
CRP 22-01

THIS CERTIFIES THAT THE UNDERSIGNED HAS EXAMINED THE LOCATION OF THE PROPOSED PROJECT, AND THAT THE PLANS, SPECIFICATIONS AND CONTRACT GOVERNING THE WORK EMBRACED IN THIS IMPROVEMENT, AND THE METHOD BY WHICH PAYMENT WILL BE MADE FOR SAID WORK IS UNDERSTOOD. THE UNDERSIGNED HEREBY PROPOSES TO UNDERTAKE AND COMPLETE THE WORK EMBRACED IN THIS IMPROVEMENT, OR AS MUCH THEREOF AS CAN BE COMPLETED WITH THE MONEY AVAILABLE IN ACCORDANCE WITH THE SAID PLANS, SPECIFICATIONS AND CONTRACT, AND THE FOLLOWING SCHEDULE OF RATES AND PRICES.

(NOTE: UNIT PRICES FOR ALL ITEMS, ALL EXTENSIONS, AND TOTAL AMOUNT OF BID SHALL BE SHOWN. ALL ENTRIES MUST BE TYPED OR ENTERED IN INK.)

| ITEM NO | DESCRIPTION | PLAN QUANTITY | UNITS | UNIT PRICE | TOTAL AMOUNT |
|-------------------------------------|--|---------------|-------|------------|--------------|
| PREPARATION | | | | | |
| 1 | MOBILIZATION | 1.00 | LS | | |
| 2 | CLEARING AND GRUBBING | 18.00 | ACRE | | |
| 3 | REMOVAL OF STRUCTURE AND OBSTRUCTION | 1.00 | LS | | |
| GRADING | | | | | |
| 4 | ROADWAY EXCAVATION INCL. HAUL | 53,685.00 | CY | | |
| 5 | UNSUITABLE FOUNDATION EXCAVATION INCL. HAUL | 100.00 | CY | | |
| 6 | EMBANKMENT COMPACTION | 31,244.00 | CY | | |
| DRAINAGE | | | | | |
| 7 | DIKE | 40.00 | EA | | |
| 8 | DITCH EXCAVATION INCL. HAUL | 3,212.00 | CY | | |
| 9 | PLAIN STEEL CULV. PIPE 0.064 IN. TH. 24 IN. DIAM. | 73.00 | LF | | |
| 10 | PLAIN STEEL CULV. PIPE ARCH 0.064 IN. TH. 24 IN. SPAN. | 201.00 | LF | | |
| 11 | PLAIN STEEL CULV. PIPE ARCH 0.064 IN. TH. 18 IN. SPAN. | 170.00 | LF | | |
| SURFACING | | | | | |
| 12 | CRUSHED SURFACING BASE COURSE | 30,402.00 | CY | | |
| HOT MIX ASPHALT | | | | | |
| 13 | HMA CL. 1/2 IN. PG 64H-28 | 10,918.00 | TON | | |
| 14 | HMA FOR APPROACH CL. 1/2 IN. PG 64H-28 | 634.00 | TON | | |
| STRUCTURE | | | | | |
| 15 | STRUCTURE EXCAVATION CLASS A INCL. HAUL | 110.00 | CY | | |
| 16 | BLOCK WALL | 1,554.00 | SF | | |
| EROSION CONTROL AND PLANTING | | | | | |
| 17 | SEEDING, FERTILIZING, AND MULCHING | 12.00 | ACRE | | |
| 18 | WATTLES | 750.00 | LF | | |
| TRAFFIC | | | | | |
| 19 | PAINT LINE | 50,672.00 | LF | | |
| 20 | PROJECT TEMPORARY TRAFFIC CONTROL | 1.00 | LS | | |
| 21 | PORTABLE CHANGEABLE MESSAGE SIGN | 168.00 | HRS | | |
| 22 | REMOVE AND RESET SIGN | 2.00 | EA | | |
| 23 | PERMANENT SIGNING | 1.00 | LS | | |
| 24 | STOP BAR | 106.00 | LF | | |
| 25 | GUIDE POST TYPE W | 96.00 | EA | | |
| OTHER ITEMS | | | | | |
| 26 | STRUCTURE EXCAVATION CLASS B INCL HAUL | 116.00 | CY | | |
| 27 | GRAVEL BACKFILL FOR PIPE ZONE BEDDING | 181.00 | CY | | |
| 28 | REMOVE AND RESET FENCE | 1,100.00 | LF | | |

| ITEM NO | DESCRIPTION | PLAN QUANTITY | UNITS | UNIT PRICE | TOTAL AMOUNT |
|---|--|---------------|-------|------------------|--------------|
| OTHER ITEMS | | | | | |
| 29 | TWO-RAIL VINYL FENCE | 350.00 | LF | | |
| 30 | MAILBOX SUPPORT TYPE 1 | 22.00 | EA | | |
| 31 | MAILBOX SUPPORT TYPE 2 | 5.00 | EA | | |
| 32 | MODIFY IRRIGATION HEAD | 3.00 | EA | | |
| 33 | STRUCTURE SURVEYING | 1.00 | LS | | |
| 34 | ROADWAY SURVEYING | 1.00 | LS | | |
| 35 | TRIMMING AND CLEANUP | 1.00 | LS | | |
| 36 | SPCC PLAN | 1.00 | LS | | |
| 37 | MONUMENT TYPE 2 | 15.00 | EA | | |
| 38 | MONUMENT TYPE 3 | 39.00 | EA | | |
| 39 | MINOR CHANGE | 1.00 | DOL | \$ 30,000.00 | \$ 30,000.00 |
| | | | | SUB-TOTAL | |
| SCHEDULE B - CITY OF WALLA WALLA | | | | | |
| B1 | MOBILIZATION | 1.00 | LS | | |
| B2 | ACCESS MANHOLE CONCRETE COLLAR | 1.00 | EA | | |
| B3 | ACCESS MANHOLE ADJUSTMENT | 3.00 | EA | | |
| B4 | ACCESS MANHOLE ADJUSTMENT WITH NEW CASTING | 1.00 | EA | | |
| B5 | TEST STATION ADJUSTMENT | 15.00 | EA | | |
| B6 | TELEMETRY PEDESTAL DEMO | 2.00 | EA | | |
| B7 | TELEMETRY PEDESTAL INSTALL | 4.00 | EA | | |
| B8 | TELEMETRY CABLE | 390.00 | LF | | |
| B9 | GROUND BED DECOMMISSION | 1.00 | EA | | |
| B10 | GROUND BED INSTALL | 1.00 | EA | | |
| B11 | GROUND BED CASING | 50.00 | LF | | |
| B12 | VALVE CAN OR VALVE BOX ADJUSTMENT | 2.00 | EA | | |
| B13 | MINOR CHANGES | 1.00 | DOL | \$ 20,000.00 | \$ 20,000.00 |
| | | | | SUB-TOTAL | |

TOTAL _____