

# WEST SEATTLE CORRIDOR BRIDGE PROJECT

## VIRTUAL PRE-PROPOSAL CONFERENCE

### Hydro Demolition Package | Core Drilling Package

Monday, October 11, 2021

2:00 pm

For proposal questions and a link to attend the virtual meeting please contact Dominic Mascia (206) 620-0630 X405 or email [WestSeattleBids@KraemerNA.com](mailto:WestSeattleBids@KraemerNA.com)

**PROJECT DESCRIPTION:** The West Seattle Corridor Bridges Rehabilitation and Strengthening project includes rehabilitation of the West Seattle Bridge and Spokane Street Swing Bridge, and miscellaneous major maintenance work to the elevated structures leading up to the existing bridges. This project will rehabilitate and strengthen both bridges for use by the public.

#### SCOPE OF WORK - **HYDRO DEMOLITION:**

- Hydro Demolition to create access holes in the existing Bridge Deck and open existing 2" grouted holes as shown in the construction documents.
- Water supply and waste slurry removal/disposal is the responsibility of the subcontractor and to be considered incidental to respective items.
- The subcontractor shall include 1 mobilization(s) for the work.
- Final Cleaning of Subcontractor work area(s) to the satisfaction of the Contractor is the responsibility of the subcontractor.
- Pricing shall be valid for 60 days.
- Bid Bonds, and Payment and Performance Bonds (at subcontract execution) are required for projects over \$300,000.
- Subcontractors and suppliers seeking to work with Kraemer North America must comply with all COVID-19 vaccination requirements enacted by federal, state and/or local governmental entities that apply to the project. Your submission of a quote to Kraemer indicates that your company can comply with any such vaccination requirement(s) and that its cost to comply has been considered in your quote.

#### SCOPE OF WORK - **CORE DRILLING:**

- Core Drilling of existing pier diaphragms, walls, and floors of existing bridge as shown in the construction documents.
- Water supply and drilling waste slurry removal/disposal is the responsibility of the subcontractor and to be considered incidental to respective items.
- GPR Scanning of the concrete prior to drilling is the subcontractor's responsibility and will be required to be reviewed and approved by the City prior to the coring activities.
- Hole sizing shown in the plans can be increased/decreased to the next whole inch but must be submitted and approved by the Contractor & City prior to coring operations.
- Test hole to be utilized for utility routing as shown in the plans will require City approval prior to production coring.
- The subcontractor shall include 5 mobilizations for the work.
- Final Cleaning of Subcontractor work area(s) to the satisfaction of the Contractor is the responsibility of the subcontractor.
- Work platforms are the responsibility of the subcontractor
- Hoisting will be provided by the contractor.
- Pricing shall be valid for 60 days.
- Bid Bonds, and Payment and Performance Bonds (at subcontract execution) are required for projects over \$300,000.
- Subcontractors and suppliers seeking to work with Kraemer North America must comply with all COVID-19 vaccination requirements enacted by federal, state and/or local governmental entities that apply to the project. Your submission of a quote to Kraemer indicates that your company can comply with any such vaccination requirement(s) and that its cost to comply has been considered in your quote.

**DBE Requirement:** This Contract will have a mandatory DBE goal of 2%, Note: City of Seattle Inclusion Plan requirements are not applicable on FHWA funded projects. See Part 2 of Construction Services Contract for more information.

**CWA Requirement:** This project will have a mandatory Community Workforce Agreement (CWA) requirement. Submitting a proposal, the bidder agrees to participate and meet the requirements of the CWA.

**FOR MORE INFORMATION CONTACT:** Darling Nava, D&I Resource Specialist | 813.947-8586 | [darling@zanninc.com](mailto:darling@zanninc.com)

**TO OBTAIN BID DOCUMENTS:** [www.WestSeattlebids.com](http://www.WestSeattlebids.com)

Explicit proposal instructions can be found in the 4.0 Proposals section of the RFQ/PA documents.

**BID DUE DATE:** October 20, 2021 | 2:00 pm