

Bid Schedule – Sprague/Barker Roundabout

ITEM #	ITEM DESCRIPTION	SPECS	UNITS	QUANTITY	PRICE/ UNIT	TOTAL
100	MOBILIZATION	1-09.7	L.S.	1		
101	MINOR CHANGE	1-04.4(1)	CALC.	1	CALC.	\$25,000.00
102	CONSTRUCTION SURVEYING	1-05.4	L.S.	1		
103	ADA FEATURES SURVEYING	1-05.4	L.S.	1		
104	SPCC PLAN	1-07.15 (1)	L.S.	1		
105	PUBLIC LIAISON REPRESENTATIVE	1-07.23	L.S.	1		
106	PROJECT TEMPORARY TRAFFIC CONTROL	1-10	L.S.	1		
107	PORTABLE CHANGEABLE MESSAGE SIGN	1-10	HR.	7,000		
108	EROSION CONTROL AND WATER POLLUTION PREVENTION	8-01	L.S.	1		
109	CLEARING AND GRUBBING	2-01	ACRE	2.13		
110	LARGE TREE REMOVAL	2-02	EACH	15		
111	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	2-02	L.S.	1		
112	SAWCUT ASPHALT PAVEMENT	2-02	LF-IN	12,000		
113	REMOVE ASPHALT PAVEMENT	2-02	S.Y.	4,200		
114	REMOVE EXISTING CATCH BASIN	2-02	EACH	2		
115	ABANDON EXISTING DRYWELL	2-02	EACH	1		
116	REMOVE STORM DRAIN PIPE	2-02	L.F.	85		
117	REMOVE CEMENT CONCRETE SIDEWALK/DRIVEWAY APPROACH	2-02	S.Y.	27		
118	REMOVE CEMENT CONCRETE CURB	2-02	L.F.	140		
119	ROADWAY EXCAVATION INCL. HAUL	2-03	C.Y.	1,860		
120	TRENCH FENCE SAFETY COMPLIANCE	2-09	CALC.	1	CALC.	\$1.00
121	TRENCH EXCAVATION SAFETY SYSTEM	2-09	L.S.	1		
122	CRUSHED SURFACING TOP COURSE, 3 IN. DEPTH	4-04	S.Y.	435		
123	CRUSHED SURFACING TOP COURSE, 6 IN. DEPTH	4-04	S.Y.	700		
124	CRUSHED SURFACING TOP COURSE, 8 IN. DEPTH	4-04	S.Y.	3,750		

Bid Schedule – cont'

ITEM #	ITEM DESCRIPTION	SPECS	UNITS	QUANTITY	PRICE/ UNIT	TOTAL
125	HMA CL. 3/8" PG 64H-28 6 INCH DEPTH	5-04	S.Y.	3,750		
126	HMA CL. 3/8" PG 64H-28 MISC. AREAS	5-04	S.Y.	650		
127	JOB MIX COMPLIANCE PRICE ADJUSTMENT	5-04	CALC.	1	CALC.	\$1.00
128	COMPACTION PRICE ADJUSTMENT	5-04	CALC.	1	CALC.	\$1.00
129	UTILITY CASTING DEPTH COMPLIANCE	5-04	CALC.	1	CALC.	\$1.00
130	HMA SURFACE SMOOTHNESS COMPLIANCE	5-04	CALC.	1	CALC.	\$1.00
131	PIGMENTED CEMENT CONCRETE TRUCK APRON	5-05	S.Y.	230		
132	CEMENT CONCRETE COMPLIANCE ADJUSTMENT	5-05	CALC.	1	CALC.	\$1.00
133	DUCTILE IRON STORM SEWER PIPE 10 IN. DIA.	7-04	L.F.	403		
134	CATCH BASIN TYPE 1	7-05	EACH	4		
135	CONCRETE INLET TYPE 1	7-05	EACH	5		
136	PRECAST CONCRETE DRYWELL TYPE A WITH TYPE 4 GRATE	7-05	EACH	5		
137	SPILL CONTROL SEPARATOR	7-05	EACH	4		
138	ADJUST GAS VALVE	7-11	EACH	1		
139	ADJUST UTILITY VAULT	7-11	EACH	1		
140	ADJUST EXISTING WATER VALVE	7-12	EACH	1		
141	ADJUST EXISTING WATER VAULT	7-12	EACH	1		
142	SOD INSTALLATION	8-02	S.Y.	1,300		
143	SEEDING AND FERTILIZING	8-02	S.Y.	400		
144	TOPSOIL, TYPE A 12" IN DEPTH	8-02	S.Y.	350		
145	BARK MULCH	8-02	S.Y.	22		
146	IRRIGATION SYSTEM REVISION	8-03	EACH	5		

Bid Schedule – cont'

ITEM #	ITEM DESCRIPTION	SPECS	UNITS	QUANTITY	PRICE/ UNIT	TOTAL
147	CONCRETE SPLASH PAD	8-04	EACH	4		
148	CEMENT CONCRETE TRAFFIC CURB AND GUTTER	8-04	L.F.	1,870		
149	CEMENT CONCRETE TRAFFIC CURB	8-04	L.F.	1,450		
150	CEMENT CONCRETE PEDESTRIAN CURB	8-04	L.F.	175		
151	ROUNDAABOUT TRUCK APRON CEMENT CONCRETE CURB AND GUTTER	8-04	L.F.	270		
152	ROUNDAABOUT CENTRAL ISLAND CEMENT CONCRETE CURB	8-04	S.Y.	195		
153	TEXTURED PIGMENTED TRAFFIC ISLAND	8-05	S.Y.	800		
154	CEMENT CONCRETE DRIVEWAY APPROACH	8-06	S.Y.	250		
155	DELINEATOR AND CORE HOLE	8-10	EACH	23		
156	BULLNOSE MARKER	8-10	EACH	4		
157	TEMPORARY FENCING	8-12	L.F.	90		
158	REMOVE AND REINSTALL CHAIN LINK FENCE	8-12	L.F.	70		
159	CHAIN LINK FENCE TYPE 4	8-12	L.F.	335		
160	DOUBLE 14 FT CHAIN LINK GATE	8-12	EACH	1		
161	MONUMENT AND CASE COVER	8-13	EACH	1		
162	CEMENT CONCRETE SIDEWALK	8-14	S.Y.	600		
163	CEMENT CONCRETE CURB RAMP TYPE PARALLEL A	8-14	EACH	8		
164	DETECTABLE WARNING SURFACE	8-14	S.F.	226		
165	CEMENT CONCRETE SIDEWALK- 6 IN. DEPTH	8-14	S.Y.	180		
166	MAILBOX SUPPORT, TYPE 1	8-18	EACH	4		
167	ILLUMINATION SYSTEM	8-20	L.S.	1		
168	PERMANENT SIGNING	8-21	L.S.	1		
169	PLASTIC LINE - TYPE B	8-22	L.F.	480		
170	PLASTIC LINE	8-22	L.F.	2280		

171	PLASTIC WIDE LANE LINE	8-22	L.F.	140		
172	PLASTIC CROSSWALK LINE	8-22	S.F.	260		
173	SEGMENTAL CONCRETE RETAINING WALL	8-24	S.F.	1,592		
TOTAL BID SCHEDULE						

Person/Entity Name: _____

Signature Of Bidder: _____

Company: _____

Date: _____