

## ADDENDUM NO. 2

JUNE 26, 2018

**RE: CARLIN BAY PHASE II WASTEWATER IMPROVEMENTS**

**OWNER: CARLIN BAY PROPERTY OWNERS ASSOCIATION**

**FROM: Welch, Comer & Associates, Inc.**  
350 E. Kathleen Ave.  
Coeur d'Alene, Idaho 83815  
Phone: (208) 664-9382 Fax: (208) 664-5946

**TO: ALL PLAN HOLDERS**

The following modifications, clarifications and information are hereby made a part of the contract provisions and shall be fully binding.

This Addendum consists of **3** pages: 2 Addendum pages and 1 Attachment page.

**IMPORTANT:** Bidders must acknowledge receipt of this Addendum as well as all other issued addenda on the Bid Form provided with the Contract Documents, which must be utilized by Bidder for bid to be considered responsive. Failure to do so may subject Bidder to disqualification.

### **TECHNICAL SPECIFICATIONS:**

With reference to **Section 01 1000, Paragraph 1.07.C**, is revised to read as follows:

- C. Substantial Completion: The work shall be substantially completed within 120 calendar days of the notice to proceed. Notice to proceed is anticipated to be issued June 30, 2018.

With reference to **Section 31 2316, Paragraph 1.02.A**, please delete in its entirety.

With reference to **Section 32 3113, Paragraph 1.03.D**, is revised to read as follows:

- D. This section shall be paid under the following Pay Items:

<u>Pay Item</u>	<u>Description</u>	<u>Pay Unit</u>
323113.01	Chain Link Fencing	LF
323113.06	12' Swing Gate	EA

### **CLARIFICATION:**

1. Notice to proceed is anticipated to be issued on or about June 30<sup>th</sup>, to allow lead time for ordering liner materials. Due to site conditions, Contractor should not plan on moving on site prior to August 15<sup>th</sup> for work inside the lagoon.
2. There will be two 12' swing gates. The other will be placed at the western entrance to the dike.

3. Liner bedding material to be smooth rolled prior to liner placement.
4. Sump for intake screen will be constructed by others.
5. Safety ladders to be incidental to HDPE liner.
6. Rough grading of pond interior to be by others.
7. Bedrock will likely be encountered in pond bottom requiring adjustments of underdrain layout. Rock excavation is not anticipated.
8. Existing 6" pipe penetration will be located for Contractor in the field.

### **Attachments**

Revised Unit Prices Form

**END OF ADDENDUM 2**

# SECTION 00 4322 – UNIT PRICES FORM

## CARLIN BAY PROPERTY OWNERS ASSOCIATION CARLIN BAY PHASE II WASTEWATER IMPROVEMENTS

BASE BID					
Pay Item No.	Description	Unit	Estimated Quantity	Unit Price	Price
015050.01	Mobilization	LS	1	\$	\$
31231613.01	Underdrain Trench Excavation	LF	2430	\$	\$
312323.17	Import HDPE Liner Bedding	CY	1350	\$	\$
323113.01	Chain Link Fencing	LF	2350	\$	\$
323113.06	12' Swing Gate	EA	2	\$	\$
333111.34	4" Perforated PVC Drain Pipe	LF	2430	\$	\$
333813.01	Textured HDPE Liner	SY	24500	\$	\$
333813.02	Geotextile Liner Pad	SY	24500	\$	\$
333813.03	Life Ring Assembly	EA	6	\$	\$
TOTAL BASE BID PRICE:					\$