

## **ADDENDUM No. 1**

### **Hayden Area Regional Sewer Board (HARSB) HARSB Phase 2 Tertiary Treatment and Biosolids Project Kootenai County, Idaho**

July 30<sup>th</sup>, 2021

Addendum No. 1 to the **HARSB Phase 2 Tertiary Treatment and Biosolids Project** Bidding Documents prepared by J-U-B Engineers, Inc., WesTech Engineering, and Aqua Engineering is hereby submitted for use in bid preparation and submittal. The following clarifications, corrections, or changes are hereby made as fully and completely as if the same were entirely set forth in the Bidding Documents, and shall become an integral part of any contract entered into between the Owner and Contractor for this project.

### **GENERAL**

#### **PRE-BID MEETING:**

Notes, sign-in sheet, and powerpoint from the Pre-Bid Meeting are **attached**.

#### **COMBINED SITE CIVIL AND YARD PIPING PDFs:**

At the Contractors' request, a Combined Site Civil Exhibit and Combined Yard Piping Exhibit are **attached**. These two exhibits combine the information presented in the plan areas shown on the CG and CU sheets in Volume 4. These exhibits are not part of the Contract Documents and have been prepared solely as a convenience for the Contractor in visualization of the project extents. While these exhibits are generally believed to be reliable, the only documents the Contractor may legally rely upon are the Contract Documents.

### **VOLUME 1 – BIDDING AND AGREEMENT FORMS**

#### **ADVERTISEMENT:**

Revise any and all references to the **Bid Opening time to 2:00 pm local time**. The bid opening date remains the same.

Revise the following list of prequalified electrical subcontractors as follows:

- Revise "B&B Electric" to read "B&E Electric"
- Revise "Shannon Electrical Contractors" to read "Shannon Industrial Contractors"

#### **ISPMC 00200 - INSTRUCTION TO BIDDERS:**

Revise Article 19.08 as follows:

"19.08: Determination of the Lowest Bid price shall be based on the TOTAL BID PRICE = Base Bid plus the sum of all Additive Alternates."

**SECTION 4-A DAVIS-BACON PREVAILING WAGE DECISION:**

Add the attached document to Section 4A Davis-Bacon Prevailing Wage Decision, titled: Guidance regarding the “List of Previously Conformed Additional Classifications”. The document is **attached** to this addendum (2 pages).

**VOLUME 2 – TECHNICAL SPECIFICATIONS (Divisions 1-15)**

**SECTION 01300 – SUBMITTALS**

Replace Subsection 1.4.N with the following:

“Submitted data, equipment, and O&M information shall be HARSB project specific. Submittal information that is conflicting, irrelevant, or not specific to the Project shall be deleted or whited out not to be visible by the Contractor during the mark-up and prior to submission. Submittal information not conforming to this standard shall be returned for correction and will require resubmittal prior to approval.”

See example of acceptable submittal below.

**HARSB SUBMITTAL EXAMPLE**

VENDOR’S ORIGINAL

CONTRACTOR’S MARKUP FOR HARSB SUBMITTAL

BLANK OUT VENDOR INFORMATION THAT DOES NOT APPLY TO THE HARSB PROJECT

Replace Subsection **1.5.B** with the following:

“Unless otherwise specified, within 21 calendar days after receipt of a submittal for review and comment, the Engineer shall review the submittal and provide comments and/or markups as necessary. The Engineer’s review will result in the following submittal review designations:

1. No Exceptions Taken – does not require resubmittal
2. Revise and Resubmit – requires resubmittal
3. Rejected – requires resubmittal
4. Submit Specific Item – requires resubmittal”

Update submittal timeframe stated in **1.15.C** as follows:

“All submittals, unless noted otherwise in the Contract Documents, shall be submitted within one hundred and twenty (120) days from the Notice to Proceed...”

## **SECTION 01625 – OWNER FURNISHED EQUIPMENT AND MATERIALS COORDINATION AND INSTALLATION**

Add the following paragraph 1.6 SUBMITTALS:

### 1.6 SUBMITTALS:

- A. Contractor to compare vendor provided drawings (Owner Furnished items) and submittal data in Volume 7 through 11 for of Owner Furnished Materials and Equipment and cross-reference with Design Contract Documents.
  1. Submit cross-reference shop drawing information to Owner and Engineer for review. Shop drawings shall show layout and interfacing elements of Owner Furnished items with Contractor furnished foundations, and structures including but not limited-to, anchor bolt and mounting layouts, connections to related components and piping, and electrical connection points. Identify any discrepancies between the Contract Documents and the Owner-Furnished equipment information and notify Owner and Engineer.
  2. Owner and Engineer will review Contractor's submittal information including any identified discrepancies. Incomplete submittals will be rejected.

## **SECTION 03350 – Concrete Finishing**

Add the following under 2.2.A.1 – Manufacturers:

- “f. Liqui-Hard”

## **SECTION 15184 – Solar Dryer Radiant Heating System Piping**

Replace paragraph 2.2.F.1.d with paragraph below. The size of piping is corrected to ¾” from currently listed 4/4”

- d. *Header assembly: In-slab reverse return header assembly shall be constructed of 3/4 inch hePEX with Engineered Polymer ASTM F1960 cold expansion fittings.*

## **VOLUME 3 – TECHNICAL SPECIFICATIONS (Division 16)**

No updates this addendum.

## **VOLUME 4 – PLANS (J-U-B Engineers, Inc)**

### **Drawing G00-013**

Modify information in pipe schedule for TEI / TER, Tertiary Equalization Influent / Return as follows:

- Size: 4" – 12"
- Installation: Buried
- Pipe Spec: PVC-P-2
- Pipe Lining: None
- Fitting Lining: E
- Pipe Joints: P, M
- Fitting Joints: M
- Max. Operating Pressure (PSI): 150
- Test Pressure (PSI) & Type or Specification: 150, H
- Remarks: --
- Pipe Solid Color: N/A

Add a new line item in the Pipe Schedule as follows:

- Legend: TEI / TER
- Service: Tertiary Equalization Influent / Return
- Size: 14" – 36"
- Installation: Buried
- Pipe Spec: PVC-P-3
- Pipe Lining: None
- Fitting Lining: E
- Pipe Joints: P, M
- Fitting Joints: M
- Max. Operating Pressure (PSI): 150
- Test Pressure (PSI) & Type or Specification: 150, H
- Remarks: --
- Pipe Solid Color: N/A

### **Drawing CU00-001**


Add excavation depth to Yard Piping Note #16 as follows:

"... Contractor responsible for providing excavation of trench to a depth of 42" below finished grade, Avista-approved sand for bedding, backfill, and compaction..."

## Drawings S42-302 and S42-306

Add callouts pointing and Membrane Feed Pump Station Wet Well and Secondary Effluent HDPE Pump Station Wet Well reading:

“Partially fill vertical HDPE wet well walls with grout in field. Wet wells will be provided with 2” ports for this activity. Refer to Volume 10 “Grout Filling Vertical Structures” for additional details.”



## Drawings S80-101, S80-102, S80-103, S80-201, S80-202, S80-204, S80-205, S80-901, S80-902, S80-903, et al

The Screw Press Platform as detailed and specified on the Drawings for the Dewatering Building is an Aluminum system. At the Contractor's option it is permissible to provide a similar system that is made from hot-dip galvanized steel. Members shall have the same outer dimensions and minimum material thickness as the indicated Aluminum system. Materials and fabrication of the provided system shall conform to the requirements of Specification Section 05500 – Metal Fabrications. All structural steel members shall be hot-dip galvanized after shop fabrication. Bolts and associated hardware may be zinc-plated. System shall be fabricated in-order-to facilitate future disassembly for equipment maintenance as indicated on the Drawings for the specified Aluminum system.

## VOLUME 5 – PLANS (WesTech Engineering)

### Sheet I42-701

Add “Note 1” within the Equipment Boundary Line around the Strainers 42-MF-STR-901 and 42-MF-STR-902.

## VOLUME 6 – PLANS (Aqua Engineering)

No updates this Addendum.

## **VOLUME 7 – PRE-PROCURED MATERIALS INFORMATION (WesTech Integrated Tertiary Treatment Equipment)**

No updates this Addendum.

## **VOLUME 8 – PRE-PROCURED MATERIALS INFORMATION (ABC Pre-Engineered Metal Buildings)**

No updates this Addendum.

## **VOLUME 9 – PRE-PROCURED MATERIALS INFORMATION (Huber Solar Dryer Equipment)**

No updates this Addendum.

## **VOLUME 10 – PRE-PROCURED MATERIALS INFORMATION (Weholite HDPE Tanks)**

### **Volume 10**

Add “For Approval” Drawings of Weholite Tanks after Weholite Installation Guide documents. These Drawings are **attached**. These drawings are informational and intended to aid the Contractor in bid development. Although the Owner and Engineer have reviewed earlier Tank drawing submittals and do not expect major deviations from the attached Drawings, these Drawings have not yet been approved for fabrication and may be subject to change. The attachment also includes a Bill of Materials identifying tank weights.


## **VOLUME 11 – PRE-PROCURED MATERIALS INFORMATION (Miscellaneous)**

No updates this addendum.

NOTICE is hereby given that this Addendum must be acknowledged on the Bid for **HARSB Phase 2 Tertiary Treatment and Biosolids Project** as evidence that the Bidder is familiar with all changes incorporated herein.

Addendum Issued by:

J-U-B ENGINEERS, Inc.



Don Bloomquist, P.E.  
Project Engineer

**ATTACHMENT -  
Guidance regarding the "List of  
Previously Conformed Additional  
Classifications"**



## Guidance regarding the “List of Previously Conformed Additional Classifications”:

- This list of previously conformed additional classifications includes wage classifications and rates that were conformed (aka approved) by the U.S. Department of Labor (USDOL) for wastewater construction projects in Kootenai County that are similar in scope of work to the HARSB Phase 2 Tertiary Treatment and Biosolids Project.
- This list is being provided for **informational purposes only**. The rates contained on this list are not a guarantee that the USDOL will conform the same classifications at the listed rates provided, nor do the project owner, engineers, or the labor monitoring specialists for the project recommend that these exact rates be used for requests for additional classifications upon project award.
- When estimating rates for additional classifications in preparing bids and when requesting additional classifications after project award, contractors must perform due diligence as suggested in the Bid Document guidance in proposing an hourly base rate and bona fide fringe benefit rate that bears a reasonable relationship to the wages listed in the Heavy Wage Decision issued for bidding for the HARSB Phase 2 Tertiary Treatment and Biosolids Project.

LIST OF PREVIOUSLY CONFORMED ADDITIONAL CLASSIFICATIONS (continued on page 2)				
Classification (In Alphabetical Order)	Base Rate	Fringe Rate	Total Prevailing Wage	Date of DOL Conformance (Approval)
Crane Operator	\$29.04	\$15.95	\$44.99	October 2020
Blow-in Insulation Installer	\$29.07	\$14.13	\$43.20	April 2021
Block Mason	\$26.01	\$12.14	\$38.15	August 2014
Concrete Saw, Walking	\$29.06	\$13.75	\$42.81	March 2021
Dozer	\$27.09	\$12.85	\$39.94	August 2014
Drywall Hanger	\$26.06	\$11.26	\$37.32	August 2014
Fence Installer	\$24.34	\$10.65	\$34.99	August 2014
Finish Roller	\$25.77	\$11.76	\$37.53	August 2014
Glazier	\$29.07	\$14.13	\$43.20	January 2021
Gradall Operator	\$26.60	\$11.76	\$38.36	August 2014
Hod Carrier	\$24.34	\$10.65	\$34.99	August 2014
Laborer: Asphalt (includes raker, shoveler, spreader & distributor)	\$22.86	\$9.40	\$32.26	November 2020
Landscape Laborer	\$18.04	\$6.60	\$24.64	August 2014
Paver Operator	\$25.78	\$11.50	\$37.28	August 2014
Pipelayer	\$24.34	\$10.65	\$34.99	August 2014
Pump Operator	\$27.12	\$17.40	\$44.52	November 2020

List continued on next page

Refrigeration & Air Conditioning Mechanic	\$34.53	\$21.17	\$55.70	April 2021
Metal Roofer	\$24.34	\$10.65	\$34.99	August 2014
Screed Operator	\$26.06	\$11.56	\$37.62	August 2014
Soft Floor Installation	\$22.58	\$6.51	\$29.09	March 2021
Subgrade Roller	\$19.99	\$7.99	\$27.98	August 2014
Tile Setter	\$21.76	\$9.81	\$31.57	September 2014
Truck Driver - Mixer	\$27.12	\$17.40	\$44.52	November 2020


**ATTACHMENT -  
Weholite "For Approval" Drawings  
(Volume 10)**

Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

132 RSC250 TANKS LAYOUT BOM/ DWG NO:2511						
ITEM	DESCRIPTION	DWG NO	WT LB/UNIT	QTY	NOTE	
1	132 RSC250 X 40 FT STORAGE TANK A1	2511-1	16,500	1		
2	30 RSC160 RISER EXTENSION FOR TANK A1	2511-1A	260	1		
3	132 RSC250 X 18 FT STORAGE TANK A2	2511-2	9,500	1		
4	30 RSC160 RISER EXTENSION FOR TANK A2	2511-2A	260	1		
5	132 RSC250 X 43.3 FT STORAGE TANK B1	2511-3	18,500	1		
6	30 RSC160 RISER EXTENSION FOR TANK B1	2511-3A	160	1		
7	132 RSC250 X 33FT STORAGE TABK B2	2511-4	16,500	1		
8	30 RSC160 RISER EXTENSION FOR TANK B2	2511-4A	160	1		
9	132 R250 X 18.2 FT MEMERANE FEED PS HDPE WET WELL	2511-5	13,000	1	7050	GROUT WEIGHT IN PROFILES BY OTHERS
10	132RSC250 X 22.2 FT SECONDARY EFFLUENT PS HDPE WET WELL	2511-6	14,500	1	13720	
11	36" DR17 X 35" LG HDPE PIPE PE4710		410	2		

**FOR APPROVAL**

Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development




PARTS LIST				
ITEM	DESCRIPTION	DWG NO	QTY	
1	132 RSC250 X 40 FT STORAGE TANK A1	2511-1	1	
2	30 RSC160 RISER EXTENSION FOR TANK A1	2511-1A	1	
3	132 RSC250 X 18 FT STORAGE TANK A2	2511-2	1	
4	30 RSC160 RISER EXTENSION FOR TANK A2	2511-2A	1	
5	132 RSC250 X 43.3 FT STORAGE TANK B1	2511-3	1	
6	30 RSC160 RISER EXTENSION FOR TANK B1	2511-3A	1	
7	132 RSC250 X 33FT STORAGE TABK B2	2511-4	1	
8	30 RSC160 RISER EXTENSION FOR TANK B2	2511-4A	1	
9	132 R250 X 18.2 FT MEMERANE FEED PS HDPE WET WELL	2511-5	1	
10	132RSC250 X 22.2 FT SECONDARY EFFLUENT PS HDPE WET WELL	2511-6	1	
11	36" DR17 X 35" LG HDPE PIPE PE4710		2	


**NOTES:**


- ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
- ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING,
- ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.
- ACCESS HATCH FOR MHS ARE BY OTHERS
- INFRA PIPE SOLUTIONS USED THE FOLLOWING INPUTS FOR ITS STRUCTURAL PIPE BURIAL CALCULATIONS:
  - ASTM D2321 DUMPED CLASS I EMBEDMENT MATERIAL;
  - SOIL UNIT WEIGHT OF 120 LBS/CU.FT.;
  - WATER TABLE BELOW THE PIPE INVERT;
  - 200 PSF EQUIPMENT DEAD LOAD ( NO DYNAMIC LOADING CONSIDERED)
  - MINIMUM SOIL FRICTION ANGLE = 42 DEGREE.
  - NO VEHICULAR LIVE LOAD.

4	DP	LL	DIMS CHANGED	07/09/2021
3	DP	LL	UPDATED ITEM 7,9 & 10	05/20/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY: LL		2/9/2021	TITLE: <b>132 RSC250 TANKS LAYOUT</b>	
CHECKED BY: DP		2/9/2021		
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	DWG # : <b>2511</b>	REV: 4 SHT: 1 OF 3
SIZE: B	L2	PROJECT:	OC # : OC3977	




Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

4	DP	LL	DIMS CHANGED	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY: LL		2/9/2021	TITLE: <b>132 RSC250 TANKS LAYOUT</b>	
CHECKED BY: DP		2/9/2021		
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	DWG # : <b>2511</b>	
			REV: 4	
SIZE: B	L2	PROJECT: HARSB	OC # : OC3977	
			SHT: 2 OF 3	



**SECTION A-A**



**SECTION B-B**






Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development

4	DP	LL	DIMS CHANGED	07/09/2021	
3	DP	LL	UPDATED ITEM 7,9 & 10	05/20/2021	
REV	CHK	BY	DESCRIPTION	M/D/Y	
DRAWN BY: LL		2/9/2021	TITLE: <b>132 RSC250 TANKS LAYOUT</b>		
CHECKED BY: DP		2/9/2021			
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	DWG # :	REV: 4	
		SIZE: B	L2	PROJECT: HARSB	OC # : OC3977
			<b>2511</b>	SHT: 3 OF 3	

**FOR APPROVAL**

**TOTAL WEIGHT: APPROX 16,500 LBS**

PARTS LIST			
ITEM	DESCRIPTION	DWG NO	QTY
1	132/3350 R250 STR WL X 40.0'/12.19M		1
2	30/760 R160 WEHOLITE RISER		1
3	24" DIPS DR17 X 61" LG HDPE PIPE		1
4	14" IPS DR17 X 20" LG HDPE PIPE		1
5	14 IPS DR17 PIPE WITH BUR & STUB END ASSEMBLY	2151-1C	1
6	GUSSET PLATE PE 2 X 8 X 12		4
7	P96W END PANEL WITH REINFORCED HSS ASSEMBLY	2511-1B	1



**SECTION A-A**

Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

**NOTES:**



1. ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
2. PROVIDE A PC90 ON BOTH ENDS AT THE SAME CLOCK POSITION. PROFILE CUT AS PER STD-121.
3. ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING,
4. ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.
5. SHIP ITEM ITEM 5 LOOSE AND WELD TO ITEM 4 OF TANK ON SITE.

3	DP	LL	DIMS CHANGED	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	2/9/2021	TITLE: 132 RSC250 X 40 FT STORAGE TANK A1	
CHECKED BY:	DP	2/9/2021	DWG #: 2511-1	
Infra Pipe Solutions Ltd. <small>THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	REV: 3	SHT: 1 OF 1
SIZE: B	L2	PROJECT:	OC #: OC3977	




FOR APPROVAL

PARTS LIST		
ITEM	DESCRIPTION	QTY
1	P96W WEHOPANEL 26P X 145LG	1
2	PLATE PE 1/2 X 6 X 61 1/2	6
3	HSS 5X4X1/4 X 100 LG WITH SHIM 3/4 X 3 PL	1
4	HSS 5X4X1/4 X 144 LG WITH SHIM 3/4 X 3 PL	5
5	HSS 5X4X1/4 X 134 LG WITH SHIM 3/4 X 3 PL	1
6	HSS 5X4X1/4 X 112 LG WITH SHIM 3/4 X 3 PL	1
7	HSS 5X4X1/4 X 90 LG WITH SHIM 3/4 X 3 PL	1
8	REINFORCED PAD PE 2 X 26 ID/36 OD	1



**SECTION A-A**



1  
Ø25.8 HOLE  
FOR 24 DIPS DR17 PIPE  
(WELD @ ASSY)

Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development

NOTE:  
SHIM PLATES WITH SAME LENGTH OF HSS AND PLACED AS SHOWN

1	DP	LL	DIMS CHANGED	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	5/13/2021	TITLE: P96W END PANEL WITH REINFORCED HSS ASSEMBLY	
CHECKED BY:	DP	5/13/2021	DWG #: 2511-1B	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	PROJECT: HARSB	REV: 1 SHT: 1 OF 1
SIZE: B	L2	OC #: OC3977		

4



3

2

1

PARTS LIST		
ITEM	DESCRIPTION	QTY
1	14" IPS DR17 X 100" LG HDPE PIPE F714 PE4710	1
2	14 IPS DR17 DI BACKUP RING EPOXY COXTED	1
3	14" IPS STD STUB END	1

FOR APPROVAL



Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

DRAWN BY: LL	7/9/2021	TITLE:	
CHECKED BY: DP	7/9/2021	14 IPS DR17 PIPE WITH BUR & STUB END ASSEMBLY	
<small>Infra Pipe Solutions Ltd.          THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>	UNITS: INCHES	DWG # :	REV:
		2151-1C	SHT: 1 OF 1
	SIZE: B L2	PROJECT: HARSB	OC # : OC3977

4

3





2

1

**FOR APPROVAL**

**TOTAL WEIGHT: APPROX 9,500 LBS**

PARTS LIST			
ITEM	DESCRIPTION	DWG NO	QTY
1	132/3350 R250 PC90 WL X 18.0'/5.49M		1
2	30/760 R160 WEHOLITE RISER		1
3	P96W END PANEL WITH REINFORCED HSS ASSEMBLY	2511-2B	1
5	36" IPS DR17 X 70" LG HDPE PIPE PE4710		1
7	6" DIPS DR13.5 X 18" LG HDPE PIPE		1



Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development



**NOTES:**

1. ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
2. PROVIDE A PC90 ON BOTH ENDS AT THE SAME CLOCK POSITION. PROFILE CUT AS PER STD-121.
3. ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING,
4. ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.


3	DP	LL	DIMS CHANGED	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	2/9/2021	TITLE: 132 RSC250 X 18 FT STORAGE TANK A2	
CHECKED BY:	DP	2/9/2021	DWG # : 2511-2	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	REV: 3	SHT: 1 OF 1
SIZE: B	L2	PROJECT: HARSB	OC # : OC3977	

FOR APPROVAL

PARTS LIST		
ITEM	DESCRIPTION	QTY
1	P96W WEHOPANEL 26P X 145LG	1
2	PLATE PE 1/2 X 6 X 61 1/2	6
3	HSS 5X4X1/4 X 90 LG WITH SHIM 3/4 X 3 PL	1
4	HSS 5X4X1/4 X 134 LG WITH SHIM 3/4 X 3 PL	2
5	HSS 5X4X1/4 X 144 LG WITH SHIM 3/4 X 3 PL	5
6	HSS 5X4X1/4 X 112 LG WITH SHIM 3/4 X 3 PL	2
7	12" DIPS DR17 X 33" LG HDPE PIPE	1
8	6" DIPS DR13.5 X 34" LG HDPE PIPE	1
9	GUSSET PLATE PE 1 X 8 X 12	4



**SECTION A-A**



Weholiite "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development



NOTE:  
SHIM PLATES WITH SAME LENGTH OF HSS AND PLACED AS SHOWN

1	DP	LL	ITEM 7 WAS IPS PIPE	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY: LL		5/13/2021	TITLE:	
CHECKED BY: DP		5/13/2021	<b>P96W END PANEL WITH REINFORCED HSS ASSEMBLY</b>	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES		
			<b>2511-2B</b>	SHT: 1 OF 1
SIZE: B	L2	PROJECT: HARSB	OC # : OC3977	



**FOR APPROVAL**

PARTS LIST			
ITEM	DESCRIPTION	DWG NO	QTY
1	132/3350 R250 STR WL X 43.3'/13.21M		1
2	30/760 R160 WEHOLITE RISER		1
3	P96W END PANEL WITH REINFORCED HSS ASSEMBLY	2511-3B	1

**TOTAL WEIGHT: APPROX 18,500 LBS**




**SECTION A-A**




Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development


**NOTES:**

- ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
- PROVIDE A PC90 ON BOTH ENDS AT THE SAME CLOCK POSITION. PROFILE CUT AS PER STD-121.
- ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING, 
- ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

3	DP	LL	UPDATED NOTE	07/12/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	2/9/2021	TITLE: 132 RSC250 X 43.3 FT STORAGE TANK B1	
CHECKED BY:	DP	2/9/2021	DWG # : 2511-3	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	REV: 3	SHT: 1 OF 1
SIZE: B	L2	PROJECT: HARSB	OC # : OC3977	




**FOR APPROVAL**



**SECTION A-A**

PARTS LIST		
ITEM	DESCRIPTION	QTY
1	P96W WEHOPANEL 26P X 145LG	1
2	PLATE PE 1/2 X 6 X 61 1/2	6
3	HSS 5X4X1/4 X 100 LG WITH SHIM 3/4 X 3 PL	1
4	HSS 5X4X1/4 X 122 LG WITH SHIM 3/4 X 3 PL	1
5	HSS 5X4X1/4 X 144 LG WITH SHIM 3/4 X 3 PL	5
6	HSS 5X4X1/4 X 134 LG WITH SHIM 3/4 X 3 PL	1
7	HSS 5X4X1/4 X 112 LG WITH SHIM 3/4 X 3 PL	1
8	HSS 5X4X1/4 X 90 LG WITH SHIM 3/4 X 3 PL	1



Wholiite "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development



NOTE:  
 SHIM PLATES WITH SAME LENGTH OF HSS AND PLACED AS SHOWN

DRAWN BY: LL	5/13/2021	TITLE: <b>P96W END PANEL WITH REINFORCED HSS ASSEMBLY</b>
CHECKED BY: DP	5/13/2021	
<small>Infra Pipe Solutions Ltd.          THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>	UNITS: INCHES	DWG # : <b>2511-3B</b>
<small>INFRA PIPE SOLUTIONS LTD.</small>	SIZE: B L2	PROJECT: HARSB
		REV: SHT: 1 OF 1
		OC # : OC3977



**FOR APPROVAL**

**TOTAL WEIGHT: APPROX 16,500 LBS**


PARTS LIST			
ITEM	DESCRIPTION	DWG NO	QTY
1	132/3350 RSC250 WEHOLITE		47 FT
2	MITER PLATE PE 130 ID/ 203.6 OD X 2 THK		1
3	30/760 R160 WEHOLITE RISER X 2.3 FT		1
4	P96W END PANEL WITH REINFORCED HSS ASSEMBLY	2511-4B	1
5	36" IPS DR17 X 70" LG HDPE PIPE PE4710		1
6	30" DIPS DR17 X 34" LG HDPE PIPE F714 PE4710		1
7	GUSSET PLATE PE 2 X 8 X 12		4
8	6" DIPS DR13.5 X 18" LG HDPE PIPE		1



**DETAIL VIEW C**



**SECTION A-A**




**SECTION B-B**

Weholiite "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development


**NOTES:**

1. ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
2. PROVIDE A PC90 ON BOTH ENDS AT THE SAME CLOCK POSITION. PROFILE CUT AS PER STD-121.
3. ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING,
4. ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

4	DP	LL	DIMS CHANGED	7/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	2/9/2021	TITLE: 132 RSC250 TANK B2 WITH 90D ELBOW	
CHECKED BY:	DP	2/9/2021	DWG #: 2511-4	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	REV: 4	SHT: 1 OF 1
SIZE: B	L2	PROJECT:	OC #: OC3977	




**FOR APPROVAL**



**SECTION A-A**

PARTS LIST		
ITEM	DESCRIPTION	QTY
1	P96W WEHOPANEL 26P X 145LG	1
2	PLATE PE 1/2 X 6 X 61 1/2	6
3	HSS 5X4X1/4 X 100 LG WITH SHIM 3/4 X 3 PL	1
4	HSS 5X4X1/4 X 122 LG WITH SHIM 3/4 X 3 PL	1
5	HSS 5X4X1/4 X 144 LG WITH SHIM 3/4 X 3 PL	3
6	HSS 5X4X1/4 X 134 LG WITH SHIM 3/4 X 3 PL	2
7	HSS 5X4X1/4 X 112 LG WITH SHIM 3/4 X 3 PL	1
8	HSS 5X4X1/4 X 90 LG WITH SHIM 3/4 X 3 PL	1
9	REINFORCED PAD PE 2 X 32 ID/42 OD	1



Ø32 HOLE  
FOR 30 DIPS DR17 PIPE  
(WELD @ ASSY)



NOTE:  
SHIM PLATES WITH SAME LENGTH OF HSS AND PLACED AS SHOWN

Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development

1	DP	LL	DIMS CHANGED	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	5/13/2021	TITLE: <b>P96W END PANEL WITH REINFORCED HSS ASSEMBLY</b>	
CHECKED BY:	DP	5/13/2021	DWG # : <b>2511-4B</b>	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>				REV: 1 SHT: 1 OF 1
SIZE: B	L2	PROJECT: HARSB	OC # : OC3977	




**FOR APPROVAL**



**SECTION A-A**

30 RSC160 RISER EXTENSION TABLE				
DWG NO	DESCRIPTION	USED FOR	LG (IN)	WT LB
2511-1A	FOR TANK A1	TANK A1	84	260
2511-2A	FOR TANK TA2	TANK A2	84	260
2511-3A	FOR TANK TB1	TANK TB1	47	160
2511-4A	FOR TANK TB2	TANK TB2	47	165

PARTS LIST		
ITEM	DESCRIPTION	QTY
1	30/760 R160 PC90 WL LG SEE TABLE	1
2	TOP RING PE 35 OD/29 ID X 1/2 THK	1






Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

2	DP	LL	DIMS CHANGED	07/09/2021
1	DP	LL	DIMS CHANGED	03/23/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	2/9/2021	TITLE: 30 RSC160 RISER EXTENSION FOR TANKS	
CHECKED BY:	DP	2/9/2021		
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	DWG # :	REV: 2
		SIZE: B	L2	SHT: 1 OF 1
			PROJECT: HARSB	OC # : OC3977




Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

**FOR APPROVAL**



PARTS LIST			
ITEM	DESCRIPTION	DWG NO	QTY
1	132 R250X 20 FT DP PS P96W BASE		1
2	18" DIPS DR17 FLANGE ADAPTER		1
3	18" DIPS DR17 X 12" LG HDPE PIPE PE4710		1
4	18" DIPS BACK-UP RING IPP OR EQUIV. CL150 BOLT CIRCLE, MATES W/ ANSI B16.5, B16.1, AWWA C207		1
5	LIFTING LUG MADE FROM PE PLATE		4
6	132/3050 RSC250 X 18 FT VERT WELL BODY		1
7	REINFORCED P96W TOP COVER ASSEMBLY	2511-6A	1
8	36" IPS DR17 X 25" LG HDPE PIPE F714 PE4710		1
9	6" DIPS DR13.5 X 18" LG HDPE PIPE		1
10	2" IPS CLEAN OUT PLUG RAHN # 3153-2-2		2
11	2" IPS CLEAN OUT ADAPTER RAHN # 3153-1-2		2

- NOTES:**
- ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
  - PROVIDE STRAIGHT CUT ON BOTH ENDS.
  - ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING,
  - ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.
  - INFRA PIPE SOLUTIONS USED THE FOLLOWING INPUTS FOR ITS STRUCTURAL ASTM F1759 CALCULATIONS AND FEA ANALYSIS:
    - ASTM D2321 DUMPED CLASS I EMBEDMENT MATERIAL;
    - SOIL UNIT WEIGHT OF 120 LBS/CU.FT.;
    - WATER TABLE BELOW THE STRUCTURE;
    - MINIMUM SOIL FRICTION ANGLE = 42 DEGREE.
    - NO VEHICULAR LIVE LOAD.




3	DP	LL	UPDATED TOP AND ITEM	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	3/23/2021	TITLE:	132 R250 X 18.8 FT MEMERANE FEED PS HDPE WET WELL
CHECKED BY:	DP	3/23/2021		
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>			UNITS: INCHES 	DWG # : 2511-5
SIZE: B	L2	PROJECT: HARSB	PROJECT # : OC3977	REV: 3 SHT: 1 OF 1

Weholilte "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication - Provided to Contractor to aid in Bid Development

**FOR APPROVAL**

PARTS LIST			
ITEM	DESCRIPTION	SUBJECT	QTY
1	132 R250X 20 FT DP PS P96W BASE		1
2	36" IPS DR17 X 25" LG HDPE PIPE F714 PE4710		1
3	132/3050 RSC250 X 22 FT VERT WELL BODY		1
4	18" IPS DR17 X 20" LG HDPE PIPE F714 PE4710		1
5	REINFORCED P96W TOP COVER ASSEMBLY	2511-6A	1
6	LIFTING LUG MADE PE PLATE		4
7	18" DIPS DR17 X 12" LG HDPE PIPE PE4710		1
8	18" DIPS DR17 FLANGE ADAPTER		1
9	18" DIPS BACK-UP RING IPP OR EQUIV. CL150 BOLT CIRCLE, MATES W/ ANSI B16.5, B16.1, AWWA C207		1
10	2" IPS CLEAN OUT ADAPTER RAHN # 3153-1-2		5
11	2" IPS CLEAN OUT PLUG RAHN # 3153-2-2		5





**NOTES:**


1. ALL DIMENSIONS APPLY @ 23°C ±2°, ACTUAL LENGTHS WILL VARY BASED ON AMBIENT TEMPERATURE.
2. PROVIDE STRAIGHT CUT ON BOTH ENDS.
3. ALL WELDS ARE MADE USING MANUAL EXTRUSION WELDING,
4. ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.
5. INFRA PIPE SOLUTIONS USED THE FOLLOWING INPUTS FOR ITS STRUCTURAL ASTM F1759 CALCULATIONS AND FEA ANALYSIS:
  - 1). ASTM D2321 DUMPED CLASS I EMBEDMENT MATERIAL;
  - 2). SOIL UNIT WEIGHT OF 120 LBS/CU.FT.;
  - 3). WATER TABLE BELOW THE STRUCTURE;
  - 4). MINIMUM SOIL FRICTION ANGLE = 42 DEGREE.
  - 5). NO VEHICULAR LIVE LOAD.

3	DP	LL	DIMS CHANGED	07/09/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY:	LL	3/23/2021	TITLE: 132RSC250 X 22.8 FT SECONDARY EFFLUENT PS HDPE WET WELL	
CHECKED BY:	DP	3/23/2021	DWG #: 2511-6	
<small>Infra Pipe Solutions Ltd. THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.</small>		UNITS: INCHES	PROJECT: HARSB	PROJECT #: OC3977
SIZE: B	L2		REV: 3	SHT: 1 OF 1


**FOR APPROVAL**




PARTS LIST		
ITEM	DESCRIPTION	QTY
1	P96W WEHOPANEL 27P X 146LG	1
2	PLATE PE 1/2 X 6 X 61 1/2	6
3	16" IPS DR 17 X 45 LG HDPE PIPE PE4710	3
4	6" IPS DR 17 X 30 LG HDPE PIPE PE4710	1
5	24/610 R160 WEHOLITE RISER	1
6	TOP RING PE 28 OD/23 ID X 1/2 THK	1
7	24" HDPE LID w/4" LG SS LAG SCREW SEAL-R #24L OR EQUAL.	1
8	HSS 5X4X1/4 X 144 LG WITH SHIM 3/4 X 3 PL	2
9	HSS 5X4X1/4 X 134 LG WITH SHIM 3/4 X 3 PL	2
10	HSS 5X4X1/4 X 102 LG WITH SHIM 3/4 X 3 PL	1
11	PE GUSSET 2 X 12 X 16 CUT TO SHAPE	2



**ONLY SHOW PANEL AND HSS IN THIS VIEW**



**SECTION A-A**




**SECTION B-B**

2	DP	LL	DIMS CHANGED	07/09/2021
1	DP	LL	ITEM 10 LG AND LOCATION CHANGED	05/20/2021
REV	CHK	BY	DESCRIPTION	M/D/Y
DRAWN BY: LL		5/14/2021	TITLE: <b>P96W TOP ASSEMBLY FOR 132 RSC250 PUMP STATION</b>	
CHECKED BY: DP		5/14/2021		
UNITS: INCHES		DWG # : <b>2511-6A</b>		
SIZE: B		L2	PROJECT: HARBS	REV: 2 SHT: 1 OF 2
			OC # : OC3977	



Weholilte "For Approval" Tank Drawings (7/29/21)  
Informational and not yet approved for fabrication -  
Provided to Contractor to aid in Bid Development

Infra Pipe Solutions Ltd.  
THIS DRAWING/DOCUMENT IS INTENDED FOR THE RECIPIENT ONLY, AND ITS CONTENTS MAY CONTAIN COPYRIGHT PROTECTED, PATENTED, OR LEGALLY PRIVILEGED INFORMATION. ANY DISSEMINATION, DISTRIBUTION, COPYING OR USE OF INFORMATION CONTAINED HEREIN WITHOUT PRIOR WRITTEN PERMISSION OF AN OFFICER OF INFRA PIPE SOLUTIONS LTD. IS STRICTLY PROHIBITED.





**BOTTOM VIEW**



**PE GUSSET 2 X 12 X 16 CUT TO SHAPE**



Weholite "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

DRAWN BY: LL	5/14/2021	TITLE: <b>P96W TOP ASSEMBLY FOR 132 RSC250 PUMP STATION</b>	
CHECKED BY: DP	5/14/2021		
<small>Infra Pipe Solutions Ltd.          THIS DRAWING/DOCUMENT IS          INTENDED FOR THE RECIPIENT ONLY,          AND ITS CONTENTS MAY CONTAIN          COPYRIGHT PROTECTED, PATENTED, OR          LEGALLY PRIVILEGED INFORMATION.          ANY DISSEMINATION, DISTRIBUTION,          COPYING OR USE OF INFORMATION          CONTAINED HEREIN WITHOUT PRIOR          WRITTEN PERMISSION OF AN OFFICER          OF INFRA PIPE SOLUTIONS LTD. IS          STRICTLY PROHIBITED.</small>	UNITS: INCHES	DWG # : <b>2511-6A</b>	REV: 2 SHT: 2 OF 2
SIZE: B	L2	PROJECT: HARBS	OC # : OC3977

Material: Ductile Iron, ASTM A536, 65/45/12

REVISION HISTORY		
REV	DESCRIPTION	DATE
1	ORIGINAL	08/01/11

Dimensions											
Pipe Diameter (in)	O.D.	T	I.D.	Y	Bolt Count	Bolt Hole Size (H)	Bolt Hole Circle (BC)	R	Weight (lbs)	HDPE Operating Pressure	Steel Operating Pressure
4"	9.000	0.940	4.900	0.270	8	0.750	7.500	0.440	5.1	267	267
6"	<b>11.000</b>	<b>1.000</b>	<b>7.000</b>	<b>0.280</b>	<b>8</b>	<b>0.880</b>	<b>9.500</b>	<b>0.500</b>	<b>7.0</b>	<b>267</b>	<b>267</b>
8"	13.500	1.120	9.130	0.300	8	0.880	11.750	0.500	10.5	267	267
10"	<b>16.000</b>	<b>1.190</b>	<b>11.250</b>	<b>0.600</b>	<b>12</b>	<b>1.000</b>	<b>14.250</b>	<b>0.500</b>	<b>15.3</b>	<b>267</b>	<b>267</b>
12"	19.000	1.500	13.370	0.630	12	1.000	17.000	0.500	24.4	267	267
14"	<b>21.000</b>	<b>1.630</b>	<b>15.480</b>	<b>0.700</b>	<b>12</b>	<b>1.130</b>	<b>18.750</b>	<b>0.500</b>	<b>36.1</b>	<b>200</b>	<b>267</b>
16"	23.500	1.880	17.590	0.700	16	1.130	21.250	0.500	48.3	200	267
18"	<b>25.000</b>	<b>1.750</b>	<b>19.700</b>	<b>0.880</b>	<b>16</b>	<b>1.250</b>	<b>22.750</b>	<b>0.500</b>	<b>47.9</b>	<b>200</b>	<b>267</b>
20"	27.500	2.060	21.850	0.480	20	1.250	25.000	0.500	60.7	200	267
24"	<b>32.000</b>	<b>2.130</b>	<b>26.050</b>	<b>0.600</b>	<b>20</b>	<b>1.380</b>	<b>29.500</b>	<b>0.500</b>	<b>90.4</b>	<b>200</b>	<b>267</b>



Weholite "For Approval" Tank Drawings (7/29/21)  
 Informational and not yet approved for fabrication -  
 Provided to Contractor to aid in Bid Development

Notes		
Class 150 Bolt Circle. Mates with ANSI B16.5, B16.1, AWWA C207		
Material: Tensile 65,000 psi; Yield 45,000 psi; 12% elongation		
Finish: Blue primer, Hot dipped galvanized or Epoxy coated		
DRAWN	8/1/2011	
Matt Graff		
ENG	8/2/2011	
Ellis Clark		
QA	8/1/2011	
VPOP	8/19/2011	Duncan Schlicht
TITLE		
DIPS-FM Backup Ring Submittal		
UNLESS OTHERWISE NOTED, ALL DIMENSIONS IN INCHES		SIZE PART NO
C		SALES NO
SCALE		REV 1 SHEET 1 OF 1

Ongoing engineering design efforts may affect the technical information listed in our publications.

**ATTACHMENT -  
HARSB Phase 2 PreBid Meeting  
(7/29/21) Materials**



J-U-B ENGINEERS, INC.

J-U-B COMPANIES



THE  
LANGDON  
GROUP



GATEWAY  
MAPPING  
INC.

## **PRE-BID CONFERENCE** **CONFORMED NOTES**

**PROJECT:** Hayden Area Regional Sewer Board Phase 2 Tertiary Treatment and Biosolids Project

**OWNER:** Hayden Area Regional Sewer Board (HARSB)

**DATE/ TIME:** July 21, 2021; 9:00 AM

**LOCATION:** City of Hayden City Hall  
8930 N Government Way  
Hayden, ID 83835

**ATTENDANCE:** See sign-in sheet (attached)

---

### **AGENDA**

- Introduction and Sign-in
- Project Overview
- Review Portions of the Bidding Documents
- Questions from Bidders

***Disclaimer:** The purpose of the Pre-Bid Conference is to review some (but not all) of the conditions in the Bidding Documents and provide an informal forum for the Prospective Bidders to ask questions on the Work identified in the Bidding Documents. All answers by Owner's Representative are considered informal and non-binding. Any discussion during this meeting is considered informal and only changes made by addendum shall be considered part of the Bidding Documents.*

## **1 Introduction & Sign-in**

Hayden Area Regional Sewer Board:

System Administrator – Ken Windram  
Superintendent – Brock Morrow (*Not Present*)

J-U-B Engineers:

Design Manager: Don Bloomquist, PE (***Point of Contact for Bidding Questions***)  
[dbloomquist@jub.com](mailto:dbloomquist@jub.com) , 208-376-7330  
Program Manager: Mike Conn, PE (*Not Present*)

Attendance for this meeting will be documented; see attached sign-in sheet.

## **2 Project Overview**

### **2.1 Project Summary**



The project is an upgrade and expansion of the HARSB's existing Wastewater Treatment Plant. Project components generally include:

- Installation of one new solids contact clarifier (SCC), mechanism, and other associated equipment.
- New hollow-fiber ultrafiltration units inside a building expansion for tertiary membrane treatment.
- Installation of ancillary system to support tertiary treatment including: secondary effluent pump station, membrane feed pump station, chemical feed systems, ultra-filtration membrane Clean-In-Place and neutralization systems, ultrafiltration air scour system, process air system (pneumatic valves) filtrate/backwash supply pump station, and Plant Drain Pump Station No. 2.
- New dewatering facility including polymer systems, blend tank, solids pumping and screw press equipment.
- New solar dryer facility to treat and dry dewatered biosolids.
- Site Civil, Yard Piping and supporting electrical improvements.

## 2.2 Pre-Bid Power Point

See attached for a copy of the Pre-Bid meeting power point.

# 3 Project Documents and Important Requirements

## 3.1 Organization

- Volume 1 – Bidding and Agreement Forms
  - Section 1A – Bid Forms
  - Section 1B – Contract Forms
  - Section 2 – General Conditions
  - Section 3 –Supplementary Conditions
  - Section 4 – Idaho Clean Water State Revolving Fund (CWSRF) Specifications Insert
  - Section 4A – Davis-Bacon Prevailing Wage Decision
- Volume 2 – Technical Specifications (Div. 1-15)
- Volume 3 – Technical Specifications (Div. 16)
- Volume 4 – Plans (J-U-B Engineers)
  - Generally: Survey; Site Civil; Yard Piping; Structural (SCC, CIP Bldg, UF Bldg, Dewatering Bldg); Architectural (CIP Bldg, UF Bldg, Dewatering Bldg); Building Mechanical (CIP Bldg, UF Bldg, Dewatering Bldg); Process Mechanical (Dewatering Bldg, Plant Drain Pump Station No. 2); Electrical (Site, SCC, CIP Bldg, UF Bldg, Dewatering Bldg); Instrumentation (Biosolids Dewatering, Plant Drain Pump Station No. 2)
- Volume 5– Plans (WesTech Engineering)
  - Generally: Process Mechanical and Instrumentation for Integrated Tertiary Treatment (ITT) processes, including: Secondary Effluent Pump Station, Solids Contact Clarification, Membrane Feed/Ultrafiltration Pump Station, Ultrafiltration System, Ultrafiltration Clean-In-Place and Chemical Feed Systems, Ultrafiltration Backwash System, and Compressed Air Package)

- Volume 6 – Plans (Aqua Engineering)
  - Generally: Entire design for Biosolids Treatment / Solar Dryer facility, including Structural, Architectural, Process Mechanical, Building Mechanical, Electrical, and Instrumentation.
- Volume 7 – Pre-Procured Materials Information (WesTech Integrated Tertiary Treatment Equipment)
- Volume 8 – Pre-Procured Materials Information (ABC Pre-Engineered Metal Buildings)
- Volume 9 – Pre-Procured Materials Information (Huber Solar Dryer Equipment)
- Volume 10 – Pre-Procured Materials Information (Weholite HDPE Tanks)
- Volume 11 – Pre-Procured Materials Information (Miscellaneous)

### 3.2 Volume I – Bidding and Agreement Forms

Addendum 1:  
Changed to 2:00 PM local time

#### **Section 1A – Bid Forms**

1. **Document 00030 – Advertisement for Bids:** Bids are due by ~~11:00 AM~~ <sup>2:00 PM</sup> local time Tuesday, August 31, 2021. At the Hayden Area Regional Sewer Board Wastewater Treatment Plant: 10789 N. Atlas Road, Hayden, ID 83835, and will be publicly opened in the conference room.
  - a. Electronic copies of the Bidding Documents are available for download at [www.questcdn.com](http://www.questcdn.com) per the advertisement. Project # 7920964.
  - b. Pre-Bid Meeting attendance is mandatory.
2. **Document 00040 – Bidder’s Checklist:** This list is offered as an aid to the Bidder in preparing the bid. Verify all of the items listed are provided, as a minimum.
3. **Document 00200 – Instructions to Bidders:**
  - a. Describes conditions related to the project, bid submittal, bid security, etc.
  - b. Article 11 – Substitute and “Or-Equal” Items:
    - i. The Contract, if awarded, will be on the basis of materials and equipment specified or described in the Bidding Documents without consideration of possible substitute or “or-equal” items. Whenever it is specified or described in the Bidding Documents that a substitute or “or-equal” item of material or equipment may be furnished or used by Contractor if acceptable to Engineer, application for such acceptance will not be considered by Engineer until after the Effective Date of the Agreement. The procedure for submission of any such application by the Contractor and consideration by the Engineer is set forth in the General Conditions, Owners Supplementary Conditions, and/or individual Technical Specifications.
  - c. Article 19 – Evaluation of Bids and Award of Contract
    - i. “Owner reserves the right to reject any or all Bids, including without limitation, nonconforming, nonresponsive, unbalanced, or conditional Bids. Owner also reserves the right to waive all informalities not involving price, time, or changes in the Work and to negotiate contract terms with the Successful Bidder.” (19.01)
    - ii. “If the Contract is to be awarded, Owner will award the Contract to the Bidder submitting the lowest responsive bid who has also complied with the statutory and administrative requirements of the bid process and who holds the requisite licenses.” (19.06)

- iii. “Determination of the lowest Bid price shall be based on the Total Bid Price – Base Bid plus the sum of all Additive Alternates 1, 2, 3, 4, and 5.” (19.08)
  - d. Article 25 – Prevailing Wage Rates
    - iv. “Contractors are required to pay prevailing wage rates in accordance with the Davis-Bacon Act on this project. Refer to Section 4 of the Project Manual for current prevailing wage/Davis-Bacon wage determinations.” (25.01)
  - e. Article 26 – Funding Agency Requirements
    - v. “This project is funded in part by Idaho Department of Environmental Quality (IDEQ) State Revolving Loan Fund (SRF) funds. Contractors are required to comply with all funding agency requirements which are included in Volume 1, Section 4. Contractor’s attention is further directed to Volume 1, Section 4 which includes compliance measures for the Environmental Protection Agency (EPA)’s Clean Water State Revolving Fund (CWSRF) American Iron and Steel (AIS) Requirements.” (26.01)
- 2. Document 00410 – Bid Form**
- a. Article 2.01: Bid will remain subject to acceptance for 60 days after Bid Opening – allows HARSB review and concurrence by funding agencies.
  - b. Article 5.01: Basis of Bid
    - i. Total Bid Price – the sum of the below
      - 1. Base Bid: WWTP Improvements (All Work Under Contract Documents Except Those Items Listed Separately Below)
      - 2. Additive Alternate No. 1: Biosolids Treatment Train 2 Equipment
      - 3. Additive Alternate No. 2: Additional AC Paving Extents
      - 4. Additive Alternate No. 3: Utility Water Yard Piping Extension
      - 5. Additive Alternate No. 4: Plant Drain PS No. 2 Forecmain size increase
      - 6. Additive Alternate No. 5: Ground to Air Heat Transfer System
    - c. Article 7.01.B: “Bidder shall include in his Bid the name, or names and address, or addresses, and Idaho Public Works Contractor License Numbers of the Subcontractors who shall, in the event the Bidder secures the Contract, subcontract the plumbing, heating and air-conditioning work, and electrical work under the general Contract” – Use Document 00440.
- 3. Document 00415 – Contractor’s Non-Collusion Affidavit**
- 4. Document 00420 – Anti-Discrimination Affidavit**
- 5. Document 00430 – Bid Bond – Penal Sum Form**
- 6. Document 00440 – Naming of Subcontractors Form**

## **Section 1B – Contract Forms**

- 1. Document 00500 – Successful Bidder’s Checklist**

2. **Document 00510 – Notice of Award**
3. **Document 00520 – Agreement**
  - a. Conditions of the Agreement, including scope of the Contract Documents.
  - b. Contract Days: “The Work will be substantially completed within **410 calendar days** after the date when the Contract Times commence to run as provided in Paragraph 2.03 of the General Conditions & SC-2.03, and completed and ready for final payment in accordance with Paragraph 14.07 of the General Conditions within **440 calendar days** after the date when the Contract Times commence to run.” (4.02)
  - c. American Iron and Steel Compliance (10.06): “The Required AIS Construction Contract Clause from the Idaho Clean Water State Revolving Fund (CWSRF) Specifications Insert (Volume 1, Section 4, Article I.12.b) is hereby included by reference.”
4. **Document 00550 – Notice to Proceed**
5. **Document 00610 – Performance Bond**
6. **Document 00615 – Payment Bond**
7. **WH-5 Public Works Contract Report**
8. **Document 00620 – Contractor’s Application for Payment**
9. **Document 00625 – Certificate of Substantial Completion**
10. **Document 00940 – Work Change Directive**
11. **Document 00941 – Change Order**
12. **Document 00942 – Field Order**
13. **Document 00950 – Contractors Tax Affidavit**

## **Section 2 – General Conditions**

1. 2015 ISPWC Division 100 – Standard General Conditions to the Construction Contract
2. Section 6.09.D:

“Idaho Code Section 44-1002 requires the following: The Contractor must employ ninety-five percent (95%) bona fide Idaho residents as employees on any job under any such contract except where under such contracts fifty (50) or less persons are employed, the Contractor may employ ten percent (10%) nonresidents, provided, however, in all cases employers must give preference to the employment of bona fide residents in the performance of said work, and no contract shall be let to any person, firm, association, or corporation refusing to execute an agreement with the above mentioned provisions in it; provided that, in contracts involving the expenditure of federal aid funds this act shall not be enforced in such a manner as to conflict with or be contrary to the federal statues prescribing a labor preference to honorably discharged soldiers, sailors, and marines, prohibiting as unlawful any other preference or discrimination among citizens of the United States.”

## **Section 3 – Supplementary Conditions**

1. Amends or supplements the General Conditions

2. SC-14.02.C.1: This paragraph has been revised to allow the Owner forty-five (45) days after presentation of the Application for Payment to Owner with Engineer’s recommendation before payment becomes due.

#### **Section 4 – Idaho Clean Water State Revolving Fund (CWSRF) Specifications Insert**

1. Point of Contact: Chris Westerman, EI, IDEQ, [Chris.Westerman@deq.idaho.gov](mailto:Chris.Westerman@deq.idaho.gov), (208.666.4611)
2. Reference Part P Submissions for items required by all Bidders as part of the sealed bid, by the Successful Bidder prior to issuance of the Authorization to Award, by the Successful Bidder to the Loan Recipient prior to the issuance of the Notice to Proceed, and by subcontractors after project completion. Additional forms and requirements apply.

#### **Section 5 – Davis-Bacon Prevailing Wage Decision**

1. Point of Contact: Dorian Komberec, Community Development Specialist, Panhandle Area Council, [dkomberec@pacni.org](mailto:dkomberec@pacni.org), (208) 772-0584 ext. 310 ?

### **3.3 Volume II – Technical Specifications – Divisions 1-15**

#### **1. Section 01010 Summary of Work**

#### **2. Section 01011 Geotechnical Report**

- a. Includes the geotechnical engineering evaluation used for this project (01011A).

#### **3. Section 01014 Work Sequence**

- a. Review of major work elements and work sequencing considerations (including ability to remove components or processes from service) for Contractor’s use in developing a detailed project schedule.

#### **4. Section 01025 Measurement and Payment**

- a. Basis of payment for bid items
- b. Includes requirements for the schedule of values required from the Successful Bidder following Notice of Award (1.3)
- c. Payment Application (1.6.G):
- d. Funding Agency Requirements:
  - i. Section 1.6.H: AIS documentation and compliance is required with applications for payment (reference conditions in Volume I, Section 4).
- e. Use Tax

#### **5. Section 01300 Submittals**

- a. Use of a web-based cloud construction administration system is required for the project (2.1).
- b. Submitted Data Clarity (1.4.N):
  - i. “Data or O&M information within the submittal that is conflicting, irrelevant, or not specific to the product being provided shall be clearly struck-through or deleted by the Contractor during markup and prior to submission.”

1. This will be amended by addendum.

c. Submittal Limits (1.15):

- i. “Two submittals will be permitted for each item in this section at no cost to the Contractor. The two submittals include one initial submittal and one resubmittal.
- ii. “All submittals requiring a third review by the Engineer shall be considered unresponsive and the Owner will charge the Contractor on a Time and Materials basis for the third and all subsequent reviews and all related administrative costs not to exceed \$1,000.00 for each resubmittal.”

**6. Section 01600 Materials and Equipment**

- a. “IDEQ SRF funding requires compliance with the AIS requirements for certain products and materials. Contractor shall review and comply with the requirements contained in Volume I, Section 4. Contractor’s attention is also directed to Environmental Protection Agency (EPA) waivers that may be applicable this project.” (1.7.A)
- b. “Products and materials specified in the Contract Documents do not necessarily comply with AIS requirements. In the event a specified product or material is not AIS compliant, Contractor shall submit an equivalent product or material, or a substitution request that is AIS compliant (for review by Engineer in accordance with General Conditions, Article 6.05), or secure a product waiver from the Funding Agency. Contractor’s efforts to secure AIS-compliant products or materials shall be at no additional cost to Owner.” (1.7.B)

**7. Section 01625 Owner-Furnished Equipment and Materials Coordination and Installation**

- a. Details Contractor requirements as related to the installation and startup of Owner-furnished equipment.

**8. Section 01650 Starting of Systems**

- a. Review of major work elements and work start-up, acceptance testing and commissioning sequencing considerations for Contractor’s use in developing a detailed project schedule.

**9. Section 11000 – General Requirements for Equipment**

**10. Divisions 14 and 15**

- a. Equipment specifications are located in these divisions.
- b. Most process equipment is Owner-Furnished.

**3.4 Volume 3 – Technical Specifications – Divisions 16**

**1. Electrical specifications are located in Division 16.**

**3.5 Volumes 4-6 – Plans  
Organization**

By Discipline:

- G – General
- C – Civil
- CU – Civil Yard Piping
- CG – Site Civil / Grading
- S – Structural
- A - Architectural
- D – Process Mechanical
- CD – Civil/Process Mechanical Details
- M – Mechanical

and by Process Codes

- 00 – General, Overall, Notes, Site Work, Yard Piping
- 16 – Secondary Treatment
- 40 – Solids Contact Clarifier
- 42 – Ultrafiltration (UF)
- 48 – CIP Building / Chemical Systems
- 80 – Biosolids Dewatering
- 82 – Biosolids Treatment / Solar Dryer
- 88 – Plant Drain Pump Station No. 2

### 3.6 Volumes 7-11: Pre-Procured Materials Information

### 3.7 Addenda

1. **First Addendum tentatively planned for July 30, 2021.**

## 4 Questions

Questions submitted during the meeting via the chat feature may be answered either live as part of the meeting or by addendum (as appropriate).

## 5 Questions from Bidders / Discussion (*during meeting*)

Question: Will there be conflicting wage rates between the Building and Heavy Classifications?

Response: No, the Heavy wage decision will be the primary wage decision. The wage rates for the Heavy wage decision will supersede those on the Building wage decision. The rates common to both wage decisions have been crossed off the Building wage decision to avoid confusion.

---

Question: Can J-U-B provide Site Civil and Yard Piping CAD drawings?

Response: J-U-B will not provide CAD layouts to avoid conflicts between the Contract Documents and the CAD model. J-U-B can issue a PDF layout of the Site Civil and Yard Piping drawings on one sheet to all prospective bidders.

---

Question: What is the weight of the tanks?

Response: J-U-B will obtain this information and distribute to all prospective bidders.

---

Question: Can schedule dates be adjusted?

Response: HARSB can discuss schedule and approach in detail with the winning bidder as contract and award documents are being processed.

---

Question: Is there any way to accelerate the building construction before late spring 2022?

Response: This timeframe is an estimate based on information provided by ABC Building Corp. HARSB will follow up with ABC to refine the building delivery schedule.

---

Question: Will parts arriving on site be counted?

Response: Yes. HARSB staff will count parts and assist with shipment inventory and verification.

---

Question: Are the framing package and the skin of the building manufactured in the same location?



Response: No, they are manufactured in separate facilities.

---

Question: Can J-U-B/HARSB provide a detailed list of parts and equipment to be paid for using replacement funding?

Response: Yes. This will be provided by addendum.

---

Question: How long does Engineer have to review and return submittals?

Response: No specific engineering submittal review timeframe is identified in the Contract Documents. This will be added by addendum.

---

Question: Have products from the listed material suppliers been verified for PCB compliance?

Response: No.

---

Question: What is the lead time on owner provided MCC panels?

Response: WesTech is providing control panels per their schedule, 26-32 weeks out from the notice to commence fabrication.

---

Question:

Response:

---

**HAYDEN AREA REGIONAL SEWER BOARD (HARSB)**  
**PHASE 2 TERTIARY TREATMENT AND BIOSOLIDS PROJECT**  
**PRE-BID CONFERENCE**  
**July 21, 2021 - 9:00 am**  
**Sign in Sheet**

No.	Name	Company	Email/phone
1	Walker Noe	J-U-B	wnoe@jub.com / 208 762 8787
2	CLINT REID	PCE	CREID@powercityelectric.com/509-319-5331
3	Paul Clary	Clearwater Construction & Management	Paul@ClearwaterConstruction.US
4	Amy Jenne	Apollo	amy.jenne@pollo-gc.com
5	RUSMIR CIVIC	RSCI	steve.pierce@rscigroup.com RCIVIC@rscigroup.com
6	Chad Franks	SHANNON INDUSTRIAL	industrial@shannoncompanies.net
7	CLAY BRANT	TML CONST INC.	CLAY@TMLCONST.COM 208-818-1765
8	Matt Miller	BTE Electric inc.	matt@beelectricinc.com 208 871 3951
9	Don Bloomquist	J-U-B	dbloomquist@jub.com/ 208-813-7800
10			
11			
12			
13			
14			
15			
16			



1

## Agenda

**9:00 AM** – Introductions

**9:15 AM** – Project Overview Presentation

Ken Windram –HARSB Project Details

Don Bloomquist – Review of Project Plans

**12:00 PM** – Meeting done

2

2

## What is HARSB?

- Hayden Area Regional Sewer Board
- Joint Powers Entity providing sewer treatment for:
  - City of Hayden
  - Hayden Lake Sewer District
  - Kootenai County

3

3



4

## Project Funding

1. Idaho Department of Environmental Quality Clean Water State Revolving Loan Fund
  - City of Hayden
  - Hayden Lake Sewer District
2. HARSB Capital Reserves
3. HARSB Replacement Funds

5

5

## Project Background

- **Phase 1 Biological Nutrient Reduction (BNR):**
  - Completed December 2015
  - Provides biological phosphorus removal <0.5 mg/L
  - Included other process upgrades (headworks, flow EQ, secondary clarification, dewatering, administration facilities)
- **Phase 2 Tertiary Treatment and Biosolids:**
  - Tertiary Treatment necessary to meet final permit limits (TP<0.05 mg/L)
  - Biosolids dewatering and treatment (solar dryer)

6



7

### Phase 2 Design Team

ITT Equipment Provider and Design Engineer.

- **WesTech Engineering:** Solids Contact Clarifier and Ultra-Filtration System

Solar Dryer Engineer:

- **Aqua Engineering:** Huber Solar Dryer

Civil, Site & Dewatering Process Engineer:

- **J-U-B Engineers**

Owner Furnished Items:

PEMB, Pump Station Tanks, etc

8

## HARSB EFFLUENT PERMIT COMPLIANCE SCHEDULE

- By March 30, 2022, the permittee must provide EPA and DEQ with written notice that design has been completed and bids have been awarded to begin construction to achieve final effluent limitations.
- By March 30, 2023, the permittee must provide EPA and DEQ with written notice that construction has been completed on the facilities to achieve final effluent limitations.

9

9

## PROJECT DETAILS Don Bloomquist, P.E. JUB Engineers

10

10

## Project Schedule

### **HARSB Phase 2:**

### **Bidding, Award and Construction Schedule:**

#### Bidding Period

- **Contract Documents Issued to Bidders:** **July 16, 2021**
- **Bid Opening:** **August 31, 2021**
- **Bid Review, Budget Review, IDEQ Review of Bids:** **~early September**
- **Notice of Award** **~late September**
- **Execution of Bonds/Agreement:** **~early October**

#### Construction Period

- **Contractor Agreement Finalized:** **October 22, 2021**
- **Contractor Notice to Proceed:** **November 21, 2021**
- **Construction Period:** (410 calendar days for Construction)
- **Substantial Completion** → **January 5, 2023** IDEQ Includes 120 day IDEQ Administrative Extension to IPDES Permit was approved:
  - From 11/20/21 to 3/30/22 for IPDES milestone Part 1.D.3, and
  - From 11/20/22 to 3/30/23 for IPDES milestone Part 1.D.4

11

## Project Document Organization

Project Manual Organization	
Volume 1	Bidding and Agreement Forms
Volume 2	Technical Specifications (Divisions 1-15)
Volume 3	Technical Specifications (Division 16)
Volume 4	Plans: (J-U-B Engineers, Inc)
Volume 5	Plans: (WesTech Engineering)
Volume 6	Plans: (Aqua Engineering)
Volume 7	Procurement (ITT/WesTech)
Volume 8	Procurement (PEMB/ABC-Nucor)
Volume 9	Procurement (Solar Dryer Equipment/Huber)
Volume 10	Procurement (HDPE Tanks/Weholite)
Volume 11	Procurement (Misc Owner-Furnished Item Information)

12

12



## Contract Considerations

- Contract Assignment:
  - HARSB to retain contracts for pre-procured (Owner-Furnished) items. Coordination and installation specification for Contractor to receive, install goods and coordinate services.
- Funding:
  - IDEQ SRF Funds: 2 separate loans
  - HARSB Capital Reserve Funds
  - HARSB Replacement Funds

13

13

## Contract Considerations

- Project Contract Conditions:
  - IDEQ SRF includes American Iron and Steel Requirements
  - Davis Bacon Federal Prevailing Wage Rates
  - Panhandle Area Council (HARSB Contract Wage Administrator) over Davis Bacon Federal Prevailing Wage Rates and reporting.

14

14

## Contract Considerations

### – Schedule of Values / Contractor Invoicing

- Funding Agreements require Contractor Schedule of Values to be broken down by project elements (Ultra-Filtration, Solids Contact Clarifier, Utility Water, Dewatering, Solar Dryer) followed by a further breakdown by spec/trade divisions.
- Invoices must be received by the second (2<sup>nd</sup>) day of the month.
- Pay Applications must be approved by all 3 HARSB entities boards before payment can be made.

15

15

## Additive Alternates

- General: Additive Alternates in Section 01025
- Add Alt #1
  - Biosolids Treatment Train 2 Equipment
- Add Alt #2
  - Additional road asphalt paving
- Add Alt #3
  - Utility Water Extension
- Add Alt #4
  - Plant Drain PS No. 2 Forcemain Size Increase
- Add Alt #5
  - Solar Dryer Ground to Air Heat Transfer System


16

16

## Additive Alternate #1

- Biosolids Treatment Train 2 Equipment


- A. General Description: Additive alternate includes the installation of Biosolids Treatment Train 2 equipment including Installation of Owner-Furnished Solids Drying Bed # 2 biosolids turner mechanism (82-DR2-TRN-141), Installation of Owner-Furnished Boiler No. 2 (82-RF-BLR-202), Biosolids distribution conveyor (82-FEED-CONV-102) and Biosolids Loadout Conveyor (82-DIS-CONV-352) and other associated items. (Building, floor, radiant floor piping and building HVAC system/controls are included with Base Bid.) Reference Volume 6 Drawings for further detail.



17

## Additive Alternate #2


- Additional Road Asphalt Paving Extents



18

### Additive Alternate #3


- Utility Water Line Extension



19

### Additive Alternate #4


- Plant Drain Pump Station #2 Forcemain Size Increase



20

## Additive Alternate #5


- Solar Dryer Ground to Air Heat Transfer System



21

## Additive Alternate #5

- Solar Dryer Ground to Air Heat Transfer System



22

### Connections to Existing Systems

- General: Outlined in Sections 01014 (Work Sequence) and 01650 (Starting of Systems)
- Secondary Effluent
  - Separate pipelines from Secondary Clarifiers [#1 & #2] and [#3 & #4]
- Effluent Parshall Flume Box
  - Modifications to seal off former Secondary Effluent pipelines
  - New Ultra-Filtration Filtrate and Secondary Effluent Overflow

23

23


### Connections to Existing Systems

- Tertiary Equalization Influent/Effluent
- WAS Pipelines Extensions to Dewatering
- Plant Drain Pump Station #2 Forcemain Connection at Headworks
- Utilities
  - Utility Water
  - Potable Water
  - Natural Gas (by Avista)

24

24


### Connections to Ex. Systems - North



25

25

### Connections to Existing Systems - Sitewide



26


26

## SOLAR DRYER / DEWATERING BUILDING

 AMERICAN BUILDINGS  
A PLUMBLINE COMPANY

JOB NO. 180200  
N2180472A  
PROJECT NO. 180200  
HARSB Biosolids Drying Building

NO.	DESCRIPTION



27


27

# HARSB Project Requirements (Ken Windram)

28

28






29

<b>HARSB OWNER PROCURED EQUIPMENT FOR TERTIARY TREATMENT AND BIOSOLIDS PHASE 2 PROJECT</b>		
SUPPLIER		ESTIMATED DELIVERY DATE
WESTECH ENGINEERING	FINAL DRAWINGS REVIEW BEFORE RELEASED TO FABRICATION.	<b>26-32 week range from notice to commence fabrication to shipment</b> <b>If notice given Sept 1, shipment by June 2022</b>
WEHOLITE	RELEASED TO WEHOLITE FOR FABRICATION. 10 WEEKS FOR FABRICATION.	<b>FEBRUARY 2021</b>
HUBER	RELEASED FOR FABRICATION	<b>HUBER EQUIPMENT DELIVERED DECEMBER 2021</b>
ABC BUILDING CORP	FINAL ABC IS PRODUCING FABRICATION DRAWINGS JULY	LATE SPRING 2022
POLYBLEND POLYMER UNIT	ON SITE AT HARSB	ON SITE
3110 Gallon FRP Tank	ON SITE AT HARSB.	ON SITE
TAURUS POWER (SCADA PRG CONTRACTS SIGNED WAITING FOR PROGRAMING)		
PWTECH 2ND SCREW PRESS		SPRING 2022
HYDRASTAL PLANT DRAIN PUMP STATION 2		SPRING 2022

30



31

The cover page features the **INFRAPIPE** logo at the top right. The main title is **Weholite® Structural Profile Wall HDPE Pipe Installation Guide**, with the subtitle **VOLUME 10: Procurement (HDPE Tanks/Weholite)**. Below the text is a photograph of a construction site showing several large black HDPE pipes and tanks being prepared in a trench. A yellow excavator and a worker are visible in the scene.

32

## REPLACEMENT COSTS SEPARATED

- Replacement funding is separate from other funding sources.
- The Contractor must separate the Replacement Activities costs in the schedule of values.
- Replacement activities include ALL Dewatering equipment procurement, installation and related mechanical, electrical, structural, etc. costs.

33

33

## DEWATERING REPLACEMENT EQUIPMENT

Item	Process Area	Tag Number	Description	Sheet Reference
<del>1</del>	<del>40-SOLIDS CONTACT CLARIFIER</del>	<del>40-SCCS-P-301</del>	<del>SCC SLUDGE WASTE PUMP</del>	<del>D-80-101; VOLUME 5.P</del>
2				
3	80-BIOSOLIDS DEWATERING	80-POLS-ME-401	EXST POLYMER SYSTEM (RELOCATED)	180-701
4	80-BIOSOLIDS DEWATERING	80-POLS-ME-401	POLYMER PREPERATION SYSTEM NO.1 (ACRISON DRY AND LIQUID)	180-701
<del>5</del>	<del>80-BIOSOLIDS DEWATERING</del>	<del>80-BS-MXR-406</del>	<del>MIXER FOR SLUDGE BLEND TANK</del>	<del>180-704</del>
6	80-BIOSOLIDS DEWATERING	80-POLS-P-501	POLYMER FEED PUMP NO. 1	180-702
7	80-BIOSOLIDS DEWATERING	80-POLS-P-502	POLYMER FEED PUMP NO. 2	180-702
<del>8</del>	<del>80-BIOSOLIDS DEWATERING</del>	<del>80-DS-TNK-400</del>	<del>SLUDGE BLEND TANK</del>	<del>180-704</del>
9	80-BIOSOLIDS DEWATERING	80-POLS-ME-502	POLYMER PREPERATION SYSTEM NO.2 (POLYBLEND)	180-703
10	80-BIOSOLIDS DEWATERING	80-BS-P-404	SLUDGE FEED PUMP NO. 1	180-704
11	80-BIOSOLIDS DEWATERING	80-BS-P-405	SLUDGE FEED PUMP NO. 2	180-704
12	80-BIOSOLIDS DEWATERING	80-DWS-SCP-401	SLUDGE DEWATERING SCREW PRESS NO. 1	180-706
13	80-BIOSOLIDS DEWATERING	80-DWS-SCP-402	SLUDGE DEWATERING SCREW PRESS NO. 2	180-705
14	80-BIOSOLIDS DEWATERING	80-WAS-P-403	SLUDGE GRINDER	180-704
15	80-BIOSOLIDS DEWATERING	80-DWS-CONV-401	DEWATERED SLUDGE SCREW CONVEYOR	180-706
16	80-BIOSOLIDS DEWATERING	80-DWS-CONV-402	DEWATERED SLUDGE SCREW CONVEYOR	180-705
17				
18	88-PLANT DRAIN PUMP STA NO. 2	88-FM-P-101	PLANT DRAIN PS #2 PUMP 1	188-701
19	88-PLANT DRAIN PUMP STA NO. 2	88-FM-P-102	PLANT DRAIN PS #2 PUMP 2	188-701

34

34

# DEWATERING VALVES


80-BS-HV-403	SLUDGE BLEND TANK OUTLET VALVE
80-BS-HV-404	SLUDGE FEED PUMP 80-P-404 SUCTION VALVE
80-BS-HV-405	SLUDGE FEED PUMP 80-P-405 SUCTION VALVE
80-BS-HV-406	SLUDGE FEED PUMPS DISCHARGE CROSS OVER VALVE
80-BS-HV-407	SLUDGE FEED PUMP 80-P-404 DISCHARGE VALVE
80-BS-HV-408	SLUDGE FEED PUMP 80-P-405 DISCHARGE VALVE
80-UW-HV-410	UTILITY WATER FEED TO SCREW PRESS 1
80-UW-HV-411	UTILITY WATER FEED TO SCREW PRESS 2
80-UW-HV-412	UTILITY WATER FEED TO SCREW PRESS 2
80-UW-HV-413	UTILITY WATER FEED TO SCREW PRESS 2
80-UW-HV-420	UW BUILDING SHUT OFF
80-WAS-HV-420	WAS GRINDER INLET VALVE
80-WAS-HV-421	WAS GRINDER OUTLET VALVE
80-BS-HV-460	SLUDGE BLEND TANK INLET VALVE
80-BS-HV-461	SLUDGE MIX TANK BYPASS VALVE
80-BS-HV-470	PRESSATE VALVE TO SECONDARY EFFLUENT P.S.
80-BS-HV-471	PRESSATE VALVE TO PLANT DRAIN P.S.
80-POLS-HV-520	POLYMER AGE TANK OUTLET VALVE TO POLYMER FEED PUMPS
80-POLS-HV-522	POLYMER SOLUTION TO SCREW PRESS 1
80-POLS-HV-524	POLYMER SOLUTION TO SCREW PRESS 2
80-HWS-HV-526	HOT WATER VALVE TO DRY POLYMER SYSTEM
80-HWS-HV-527	HOT WATER VALVE TO LIQUID POLYMER SYSTEM
80-HWS-HV-528	HOT WATER VALVE TO POLYBLEND SYSTEM
80-POLS-HV-531	POLYMER FEED VALVE TO POLYMER PUMP 1
80-POLS-HV-532	POLYMER FEED VALVE TO POLYMER PUMP 2
80-POLS-HV-534	POLYMER PUMP 1 TO SCREW PRESS 1 VALVE
80-POLS-HV-535	POLYMER PUMP 1 TO SCREW PRESS 2 VALVE
80-POLS-HV-536	POLYMER PUMP 2 TO SCREW PRESS 1 VALVE
80-POLS-HV-537	POLYMER PUMP 2 TO SCREW PRESS 2 VALVE
80-POLS-HV-538	POLYBLEND POLYMER TO SCREW PRESS 1 VALVE
80-POLS-HV-539	POLYBLEND POLYMER TO SCREW PRESS 2 VALVE
80-POLS-HV-540	POLYBLEND POLYMER TO DAY TANK
80-POLS-HV-541	POLYBLEND POLYMER TO SCREW PRESS 1 & 2 VALVE
80-POLS-HV-542	POLYMER PUMP 1 DISCHARGE VALVE
80-POLS-HV-543	POLYMER PUMP 2 DISCHARGE VALVE

LAST UPDATED: 6/25/2021  
 SHEET: **015**  
 DRAWING: **G00-015**

35


35

# DEWATERING YARD PIPING




36

# DEWATERING YARD PIPING 2




37

# ELECTRICAL / SIGNAL CONDUITS TO DEWATERING BUILDING MCC ROOM




38

# ELECTRICAL / SIGNAL CONDUITS TO DEWATERING BUILDING MCC ROOM



39

# ELECTRICAL / SIGNAL CONDUITS TO DEWATERING BUILDING MCC ROOM



40

**HARSB REPLACEMENT PHASE 2 PROJECT**  
ELECTRICAL RELACEMENT DESCRIPTION

FROM SV-400 TO SV-600  
FROM PV-400 TO PV-600  
FROM PV-600 TO PV-601  
FROM SV-600 TO SV-601  
FROM SV-601 TO SV-602  
FROM PV-601 TO PV-602  
FROM PV-602 TO PV-603  
FROM SV-602 TO SV-603

DEWATERING CONDUITS AND WIRES FROM SOLAR DRYER MCC ROOM TO DEWATERING EQUIPMENT. BLEND TANK AND SCC WAS PUMP POWER AND SIGNAL CONDUITS AND WIRES DO NOT COUNT AS REPLACEMENT.

MOTOR CONTROL CENTER "MCC-DW" ALL BREAKERS EXCEPT FOR BLEND TANK MIXER, SOLIDS CONTACT CLARIFIER RAKE DRIVE, SOLIDS CONTACT CLARIFIER UNDERFLOW PUMP, SOLIDS CONTACT CLARIFIER IMPELLER DRIVE

AUTOMATIC TRANSFER SWITCH "ATS-DW"  
PANEL "PLV-DW2".  
TRANSFORMER "TX-DW2"  
TRANSFORMER "TX-DW1".

TO POWER JUNCTION BOX "JB-DW-1" AND CONTROL/ SIGNAL JUNCTION BOX "JB-DW-2".

ENCLOSED CIRCUIT BREAKER "ECB-DW-N"  
ENCLOSED CIRCUIT BREAKER "ECB-DW-E"

41

41

## Change Order Reviews

### 1.15 SUBMITTAL LIMITS

- A. Two submittals will be permitted for each item in this section at no cost to the Contractor. The two submittals include one initial submittal and one resubmittal.
- B. All submittals requiring a third review by the Engineer shall be considered unresponsive and the Owner will charge the Contractor on a Time and Materials basis for the third and all subsequent reviews and all related administrative costs not to exceed \$1,000.00 for each resubmittal.
- C. All submittals, unless noted otherwise in the Contract Documents, shall be submitted within sixty (60) days from the Notice to Proceed. Those items requiring resubmittal shall be submitted within thirty (30) days from the date of return to Contractor.

42

42

# HARSB SUBMITTAL CRITERIA

Data, equipment information or O&M information shall be HARSB project specific. Submittal information that is conflicting, irrelevant, or not specific to the project being provided shall be deleted or whited out to not be visible by the Contractor during the mark-up and prior to submission. Submittal information not conforming to this standard shall be return for correction, resubmittal prior to approval.

43

# HARSB SUBMITTAL EXAMPLE

VENDOR'S ORIGINAL

CONTRACTOR'S MARKUP FOR HARSB SUBMITTAL

**Sockets**

**Compendium**  
 RXZE2S108M  
 RXZE2S111M  
 RXZE2S114M

**Dimensions**

**ELEMECH**  
 630-499-7080 www.elemech.com

Rev:	0	Device Tag:	CR1-9
Date:	2/12/2021	Job Number:	HBR7795
Rys:	AJ	Page:	1/1
		Section:	8.1.10.10

**Sockets**

**Compendium**  
 RXZE2S108M  
 RXZE2S111M  
 RXZE2S114M

**Dimensions**

**ELEMECH**  
 630-499-7080 www.elemech.com

Rev:	0	Device Tag:	CR1-9
Date:	2/12/2021	Job Number:	HBR7795
Rys:	AJ	Page:	1/1
		Section:	8.1.10.10

BLANK OUT VENDOR INFORMATION THAT DOES NOT APPLY TO THE HARSB PROJECT

44




## HARSB TOXIC MANAGEMENT PLAN

- **Application of best management practices (BMPs) to industrial and commercial sewer customers Procurement Changes to Minimize PCBs and 2,3,7,8 TCDD**
- The plant has established a purchasing standard that equipment and materials that may contain PCB's be certified to have less than 3 parts per billion PCB levels. Equipment like a crescent wrench are not include in the PCB requirements.
- The next phase of construction to meet the Spokane River dissolved oxygen TMDL will begin in 2020. The general contractor and suppliers will be required to certify that materials used in the construction be certified to be PCB free or below 3 parts per billion.


**General Contactors will be required to provide documentation that materials like caulk, paints, lubricants, cooling fluids and similar materials are certified to be PCB free or below 3 parts per billion using EPA Test Method 8082A.**

45



46

**ATTACHMENT -  
Combined Site Civil PDF**



**COMBINED SITE CIVIL EXHIBIT:**

At the Contractors' request, a Combined Site Civil Exhibit and Combined Yard Piping Exhibit are attached. These two exhibits combine the information presented in the plan areas shown on the CG and CU sheets in Volume 4. These exhibits are not part of the Contract Documents and have been prepared solely as a convenience for the Contractor in developing bids. While these exhibits are generally believed to be reliable, the only documents the Contractor may legally rely upon are the Contract Documents.

**ATTACHMENT -  
Combined Yard Piping PDF**

## COMBINED YARD PIPING EXHIBIT:

At the Contractors' request, a Combined Site Civil Exhibit and Combined Yard Piping Exhibit are attached. These two exhibits combine the information presented in the plan areas shown on the CG and CU sheets in Volume 4. These exhibits are not part of the Contract Documents and have been prepared solely as a convenience for the Contractor in developing bids. While these exhibits are generally believed to be reliable, the only documents the Contractor may legally rely upon are the Contract Documents.

