

## **ADDENDUM NO. 1**

**TO CONTRACT DOCUMENTS FOR TOWN OF TWISP CONAYON ST – STREET & WATER MAIN IMPROVEMENTS PROJECT. THIS ADDENDUM IS DATED March 25<sup>th</sup>, 2019**

### **TO ALL PLANHOLDERS:**

The following modifications, additions, deletions, clarifications and/or information are hereby made a part of the Contract Documents and shall be fully binding upon the Contractor and the Town of Twisp.

Summary of Addendum 1 changes:

- Notifies Contractor that Contracting Agency is required to provide cultural resource monitoring during excavations associated with Schedule B of the Project. This requirement is included as a supplement to Section 1-07.16(4) Archaeological and Historical Objects.
- Revision of Bid Proposal to add Connection Detail 03 to Schedule B.

**THIS ADDENDUM MUST BE ACKNOWLEDGED ON THE BID FORM** (Page 2 of the pink sheets).

### **BID PROPOSAL**

Replace pages 2 and 3 of the Bid Proposal with those attached to this addendum.

### **SPECIAL PROVISIONS**

#### **1-07.16(4) Archaeological and Historical Objects**

(March 25, 2019 VA GSP)

Supplement this Section with the following:

A cultural resource monitor will be provided by the Contracting Agency for all excavations conducted by the Contractor under Schedule B of the Work. The Contractor shall give full cooperation to the monitor and schedule excavations in accordance with the monitor's instructions. The Contractor shall not be entitled to any claims of loss of production from the presence of the monitor or the monitor's requests. The Contractor shall account for the loss of production rate in the unit Bid prices of the Contract.

\* \* \* **END ADDENDUM 1** \* \* \*

**BID PROPOSAL**  
**Canyon St – Street & Water Main Improvements Project**

**BIDDER \_\_\_\_\_**

SCHEDULE A: TIB 2-E-886(008)-1						
NO.	DIV	ITEM	QNTY	UNIT	PRICE	EXTENDED
1	1-07	SPCC PLAN	1.00	LS		
2	1-09	MOBILIZATION	1.00	LS		
3	1-10	PROJECT TEMPORARY TRAFFIC CONTROL	1.00	LS		
4	2-03	ROADWAY EXCAVATION, INCL. HAUL	525.00	CY		
5	4-04	CRUSHED SURFACING TOP COURSE	1,570.00	TON		
6	5-04	PULVERIZE EXISTING PAVEMENT	4,875.00	SY		
7	5-04	SUBGRADE PREPARATION	4,325.00	SY		
8	5-04	HMA CL 1/2" PG 64-28	725.00	TON		
9	5-04	COMMERCIAL HMA	150.00	TON		
10	7-05	ADJUST MANHOLE	5.00	EA		
11	7-12	ADJUST VALVE BOX	8.00	EA		
12	8-01	INLET PROTECTION	1.00	EA		
13	8-01	SILT FENCE	270.00	LF		
14	8-01	EXCAVATE BIOINFILTRATION SWALE	700.00	LF		
15	8-04	CEMENT CONC. CURB WALL	30.00	LF		
16	8-13	ADJUST MONUMENT CASE AND COVER	3.00	EA		
17	8-14	CEMENT CONC. CURB RAMP TYPE, SINGLE DIRECTION	4.00	EA		
18	8-14	CEMENT CONC. CURB RAMP TYPE, DOUBLE DIRECTION	1.00	EA		
19	8-21	PERMANENT SIGNING	1.00	LS		
20	8-22	PAINTED STOP LINE	35.00	LF		
21	8-22	PAINTED CROSSWALK LINE	225.00	SF		
					SCHEDULE A TOTAL	
SCHEDULE B: RD FUNDS WATERMAIN REPLACEMENT						
NO.	DIV	ITEM	QNTY	UNIT	PRICE	EXTENDED
1	2-03	POTHOLE	5.00	EA		
2	2-09	SHORING OR EXTRA EXCAVATION CLASS B	1.00	LS		
3	7-08	PLUGGING EXISTING PIPE	7.00	EA		
4	7-09	PE WATER PIPE, 1 IN. DIAM	30.00	LF		
5	7-09	PVC PIPE FOR WATER MAIN 6 IN. DIAM.	25.00	LF		
6	7-09	DI PIPE FOR HYDRANT 6 IN. DIAM.	60.00	LF		
7	7-09	PVC PIPE FOR WATER MAIN 8 IN. DIAM.	850.00	LF		
8	7-09	CONNECTION DETAIL 01	1.00	LS		
9	7-09	CONNECTION DETAIL 02	1.00	LS		
10	7-09	CONNECTION DETAIL 03	1.00	LS		
11	7-14	SALVAGE EXISTING HYDRANT	2.00	EA		
12	7-14	HYDRANT ASSEMBLY	3.00	EA		
13	7-15	SERVICE CONNECTION 1-IN DIAM	14.00	EA		
14	7-15	SINGLE 3/4" METER AND BOX	16.00	EA		
15	7-15	DUAL 3/4" METER AND BOX	1.00	EA		
SCHEDULE C: TOWN FUNDS SEWER MAIN SPOT REPAIRS						
NO.	DIV	ITEM	QNTY	UNIT	PRICE	EXTENDED
1	7-17	SANITARY SEWER SPOT REPAIRS	1.00	LS		
					SUB TOTAL	
					8.4% SALES TAX	
					SCHEDULE C TOTAL	

**BASE BID TOTAL \_\_\_\_\_**

**BID PROPOSAL**  
**Canyon St – Street & Water Improvements Project**  
**Page 3**

BID ALTERNATE 1 - PAVE DRIVEWAYS ON EAST SIDE OF CANYON STREET STA 21+40 TO STA 25+50						
NO.	DIV	ITEM	QNTY	UNIT	PRICE	EXTENDED
1	4-04	CRUSHED SURFACING TOP COURSE	25.00	TON		
1	5-04	COMMERCIAL HMA	40.00	TON		
					ALTERNATE 1 TOTAL	

**BASE BID + ALTERNATE 1 TOTAL** \_\_\_\_\_